


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

BARBER County. Sec. 8 Twp. 31S Rge. 12W (E) (W)

Location as "NE/CNW%SW%" or footage from lines SE NW  
Lease Owner COLORADO OIL & GAS CORPORATION  
Lease Name GESS WINTER Well No. 1-8  
Office Address Denver Club Building, Denver, Colorado  
Character of Well (completed as Oil, Gas or Dry Hole) DRY HOLE  
Date well completed July 7, 19 64  
Application for plugging filed July 7, 19 64  
Application for plugging approved July 7, 19 64  
Plugging commenced July 9, 19 64  
Plugging completed July 9, 19 64  
Reason for abandonment of well or producing formation DRY HOLE

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well Herman E. Justus, Nickerson, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3900 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
<u>Soil, Sand, Shale, Redbed &amp; Shells</u>	<u>Surface Casing</u>	<u>-0-</u>	<u>250'</u>	<u>8-5/8"</u>	<u>250'</u>	<u>None</u>

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

**PLUGGED HOLE:** Filled hole with mud up to 225'. Plug with 25 sx. cement to 40'. Plug and 10 sx. cement at 40'. Put 2 sx. in rathole. Tear down.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 16 1964

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SIERRA PETROLEUM CO., INC.  
Address 1015 Wichita Plaza Bldg., Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF RUSSELL, ss.  
S. P. HALL, SUPERINTENDENT (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

S. P. Hall  
S. P. HALL, SUPT.

Box 232, Russell, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of July, 19 64

My commission expires 10-17-67

Ferry Duff  
Notary Public.

COLORADO OIL & GAS CORP. - Operator

SIERRA PETRO. CO., INC. - Contractor

GROSS-WINTER #1-8  
SE NW  
Sec. 8-31S-12W  
Barber County, Kansas

T. D.: 3900'  
Elev.: 1738' K.B.

Commenced: 6-30-64  
Completed: 7-7-64

Casing:  
8-5/8" Set at 250'

Cement:  
with 175 sx.

FORMATION	DEPTH
Soil & Sand	40
Shale	250
Redbed	650
Shale & Shells	940
Shale	1005
Blue Shale	1500
Shale w/ Lime Streaks	1600
Shale	1685
Anhydrite	1850
Lime & Shale	2230
Shale & Lime Streaks	2288
Lime	2355
Lime & Shale	3265
Shale & Lime Streaks	3530
Shale & Lime	3655
Lime & Sand	3690
Lime & Shale w/ Chalk	3835
Lime & Shale	3900

RECEIVED  
STATE CORPORATION COMMISSION

JUL 16 1964

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
                          ) ss:  
COUNTY OF RUSSELL )

I hereby certify that the above information is true and correct to the best of my knowledge.

S. P. Hill  
Superintendent

Subscribed and sworn to before me this 14th day of July, 1964.

Gray D. [Signature]  
Notary Public

My commission expires: 10-17-67