


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barber County, Sec 8 Twp. 31S Rge. 12 (E) (W) X

Location as "NE/CNW/SW" or footage from lines SE NW  
Lease Owner Wm. A. Cecil  
Lease Name Gress-Winter Well No. 1  
Office Address 722 Union Center Building Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed 8-6-64 19  
Application for plugging approved 8-7-64 19  
Plugging commenced 9-5-64 19  
Plugging completed 9-8-64 19  
Reason for abandonment of well or producing formation Dry



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie V. Elving  
Producing formation Depth to top Bottom Total Depth of Well PB 3757 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	250	None
				1 1/2	None	3114

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Rigged up.  
Working pipe. Shot pipe at 3100'. Pulling pipe.  
Pulling pipe. Plugging well. Build rock bridge at 245'. Dumped 28 sacks of cement. Filled hole and rock bridge. Capped well with 12 sacks of cement.

RECEIVED  
STATE CORPORATION COMMISSION

SEP 18 1964

CONSERVATION DIVISION

WICHITA, KANSAS

(If additional description is necessary, use BACK of this sheet)  
Name of Plugging Contractor Forbes Casing Pulling, Inc.  
Address P. O. Box 221 Great Bend, Kansas

STATE OF Kansas, COUNTY OF Barton, ss.  
J. O. Forbes (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J. O. Forbes  
P. O. Box 221 Great Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 16 day of September, 1964

My commission expires May 27, 1965 Notary Public.

COLORADO OIL & GAS CORP. - Operator

SIERRA PETRO. CO., INC. - Contractor

GRESS-WINTER #1-8  
SE NW  
Sec. 8-31S-12W  
Barber County, Kansas

T. D.: 3900'  
Elev.: 1738' K.B.

Commenced: 6-30-64  
Completed: 7-7-64

Casing:  
8-5/8" Set at 250'

Cement:  
with 175 sx.

FORMATION	DEPTH
Soil & Sand	40
Shale	250
Redbed	650
Shale & Shells	940
Shale	1005
Blue Shale	1500
Shale w/ Lime Streaks	1600
Shale	1685
Anhydrite	1850
Lime & Shale	2230
Shale & Lime Streaks	2288
Lime	2355
Lime & Shale	3265
Shale & Lime Streaks	3530
Shale & Lime	3655
Lime & Sand	3690
Lime & Shale w/ Chalk	3835
Lime & Shale	3900

RECEIVED  
STATE CORPORATION COMMISSION

OCT 29 1964

CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS )  
                          ) SS:  
COUNTY OF RUSSELL )

I hereby certify that the above information is true and correct to the best of my knowledge.

S. P. Hall  
Superintendent

Subscribed and sworn to before me this 14th day of July, 1964.

Henry Dietz  
Notary Public

My commission expires: 10-17-67