

Notice: Fill out COMPLETELY and return to Conservation Division at the address below within 60 days from plugging date.

KANSAS CORPORATION COMMISSION
OIL & GAS CONSERVATION DIVISION
WELL PLUGGING RECORD
K.A.R. 82-3-117

Form CP-4
March 2009
Type or Print on this Form
Form must be Signed
All blanks must be Filled

OPERATOR: License #: 33480
Name: BORELL, ELVERN D.
Address 1: 178 N. TURKEY RED RD.
Address 2: _____
City: DIGHTON State: KS Zip: 67839 + _____
Contact Person: KEN COLE
Phone: (785) 483-3711
Type of Well: (Check one) Oil Well Gas Well OG D&A Cathodic
 Water Supply Well Other: _____ SWD Permit #: _____
 ENHR Permit #: _____ Gas Storage Permit #: _____
Is ACO-1 filed? Yes No If not, is well log attached? Yes No
Producing Formation(s): List All (If needed attach another sheet)
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____
_____ Depth to Top: _____ Bottom: _____ T.D. _____

API No. 15 - 15-167-08310-00-00
Spot Description: _____
SE NE, SW SW Sec. 29 Twp. 15 S. R. 11 East West
978 Feet from North / South Line of Section
4158 Feet from East / West Line of Section
Footages Calculated from Nearest Outside Section Corner:
 NE NW SE SW
County: RUSSELL
Lease Name: CHEGWIDDEN Well #: B-5
Date Well Completed: _____
The plugging proposal was approved on: _____ (Date)
by: _____ (KCC District Agent's Name)
Plugging Commenced: 03/19/2013
Plugging Completed: 03/20/2013

Show depth and thickness of all water, oil and gas formations.

Oil, Gas or Water Records		Casing Record (Surface, Conductor & Production)			
Formation	Content	Casing	Size	Setting Depth	Pulled Out
		SURFACE	8.625	310	
		PRODUCTION	5.5	3214	
					KCC WICHITA
					DEC 20 2013
					RECEIVED

Describe in detail the manner in which the well is plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same depth placed from (bottom), to (top) for each plug set.

RIGGED UP FOR TUBING. RAN IN WITH BAILER. FOUND BOTTOM @ 3000'. RIGGED UP LOGTECH, PERF CASING @ 1500' AND 500'. RAN IN TUBING TO 2900'. RIGGED UP CEMENT TRUCK. PUMPED 100 SAX 60/40 POZ 4% GEL 50# HULLS @ 2900'. PULLED UP TO 1500', PUMPED 100 SAX 60/40 POZ WITH 150# HULLS. PULLED TO 500', PUMPED 70 SAX 60/40 POZ. CEMENT CIRCULATED TO THE SURFACE. PULLED REST OF TUBING. TIED TO 5 1/2", PUMPED 5 SAX CEMENT. PRESSURED TO 200#. TIED TO SURFACE, PUMPED 10 SX CEMENT. PRESSURED TO 200#. SHUT WELL IN.

Plugging Contractor License #: 31529 Name: MIKE'S TESTING & SALVAGE, INC.
Address 1: P.O. BOX 467 Address 2: _____
City: CHASE State: KS Zip: 67524 + 0467
Phone: (620) 938-2943

Name of Party Responsible for Plugging Fees: ELVERN D. BORELL
State of KANSAS County, LANE, ss.
ELVERN D. BORELL (Print Name) Employee of Operator or Operator on above-described well,

being first duly sworn on oath, says: That I have knowledge of the facts statements, and matters herein contained, and the log of the above-described well is as filed, and the same are true and correct, so help me God.

Signature: [Signature] Attorney for Elvern D. Borell

kr