

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barber

County. Sec. 35 Twp. 31 Rge. (E) 10 (W)

Location as "NE/CNWxSWx" or footage from lines 60' W of C NW SE NW

Lease Owner The Atlantic Refining Company

Lease Name Thomas J. Best

Well No. 1

Office Address 830 Kennedy Building, Tulsa, Oklahoma

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 11-10 19 56

Application for plugging filed 11-10 19 56

Application for plugging approved 11-10 19 56

Plugging commenced 11-10 19 56

Plugging completed 11-11 19 56

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production _____ 19 _____

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ma. Rives, Box 8, Pratt, Kansas

Producing formation Mississippian Depth to top _____ Bottom _____ Total Depth of Well 4600 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Heebner		3642		8-5/8"	200.86'	None
Douglas		3746				
Lansing		3833				
Kansas City		4079				
Cherokee Zone		4484				
Mississippian		4518	TD			

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

4600 - 200' heavy rotary mud
200' HONCO rubber plug
200 - 100' 30 sx. cement (regular)
100 - 40' Heavy rotary mud
40' HONCO rubber plug
40 - surf. 20 sacks regular cement

Job complete 7:15 a.m., 11-11-56.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Calvert Drilling, Inc.

Address 1008 First National Building

STATE OF Oklahoma, COUNTY OF Tulsa, ss.

Employee of owner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) J.E. Hellinghausen
J.E. Hellinghausen, Regional Drilling Manager
830 Kennedy Building, Tulsa, Oklahoma
(Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of November, 19 56

My commission expires 4-6-59

RECEIVED
STATE CORPORATION COMMISSION
Notary Public.

PLUGGING
FILE SEC. 35T.31 / 10W
BOOK PAGE 115 OF 34

NOV 27 1956
CONSERVATION DIVISION
Wichita, Kansas

THE ATLANTIC REFINING COMPANY
830 KENNEDY BUILDING
TULSA 3, OKLAHOMA

WELL LOG - Thomas J. Best No. 1

Location: 60' West of Center NW SE NW of Section 35-31-10W, Barber County, Kansas.

Lease No.: KS-10,913

Elevations: RKB 1680'; DF 1678'; GL 1669'.

Spudded: 5 p.m., 10-25-56.

Reached Total Depth: 11-9-56.

Contractor: Calvert Drilling, Inc., 1008 First National Bldg., Tulsa, Oklahoma.

Casing Record: Set 5 jts. of 8-5/8" O.D. 22.7# H-40 Spiral Weld casing at 213.05' with 200 sacks regular Monarch cement, 2% calcium chloride added.

FORMATION RECORD

0 - 96	Sand and red bed	4238 - 4329	Lime
96 - 318	Red bed	4329 - 4369	Lime, shale
318 - 1002	Red bed & shale	4369 - 4458	Lime
1002 - 1460	Red bed, shale, lime	4458 - 4499	Lime, limy chert
1460 - 1691	Shale	4497 - 4515	Lime
1691 - 1831	Shale, anhyd., lime, sand	4515 - 4568	Coring
1831 - 2131	Shale, lime, sand	4568 - 4600	Lime
2131 - 2282	Shale, lime	4600 -	Total Depth
2282 - 2436	Lime, shale		
2436 - 2516	Shale		
2516 - 2787	Shale, lime		
2787 - 2920	Shale	Heebner	3642
2920 - 3520	Shale, lime, sand	Douglas	3746
3520 - 3668	Shale	Lansing	3833
3668 - 3745	Shale, lime	Kansas City	4079
3745 - 3878	Shale, lime, sand	Cherokee	4484
3878 - 4012	Lime	Mississippian	4518
4012 - 4052	Lime, shale		
4052 - 4175	Lime		
4175 - 4238	Lime, shale		

GEOLOGIC TOPS (Sub-sea)

Heebner	3642	-1962
Douglas	3746	-2066
Lansing	3833	-2153
Kansas City	4079	-2399
Cherokee	4484	-2804
Mississippian	4518	-2838

COMPLETION

DST #1 4518-68': Tool open 1 hr., recovered 15' rathole mud, no show oil or water. ISIP 35#/17 min., IFP & FFP 30#, Hyd. 2460#, BHSIP 35#/30 min.

DRY HOLE - Plugged and abandoned 11-11-56.

STATE OF OKLAHOMA)
) SS:
COUNTY OF TULSA)

I, the undersigned, being first duly sworn upon oath, state that this well record is true, correct, and complete according to the records of this office and to the best of my knowledge and belief.

J. E. Hellinghausen
J. E. Hellinghausen
Regional Drilling Manager

Subscribed and sworn to before me this 23rd day of November, 1956.

My commission expires 4-6-59.

Wanda Davis
Wanda Davis, Notary Public

PLUGGING
FILE SEC 35 T 31 R 10W
BOOK PAGE 115 LINE 34

CEIVED
OIL AND GAS COMMISSION

DIVISION
Tulsa