


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NORTH



Locate well correctly on above
Section Plat

Barber County. Sec. 30 Twp 31S Rge. 10 (E) W (W)
Location as "NE/CNW/SW" or footage from lines NE/NE/NW
Lease Owner Anschutz Drilling Co., Inc.
Lease Name McReynolds Well No. 1
Office Address 707 Union National Bank Bldg. Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed 9-19-56 19
Application for plugging filed 9-19-56 19
Application for plugging approved 9-21-56 19
Plugging commenced 9-19-56 19
Plugging completed 9-19-56 19
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production ----- 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives, Box 8, Pratt, Kansas.
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5,030 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand, Red Bed		0	240	8-5/8"	240'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Plugged hole, Tilled hole w/heavy mud to 235', 1/4 sack hulls & plug w/20 sacks common.
Top plug @ 35' w/1/4 sack hulls & 10 sacks cement & hole plugged.

RECEIVED
STATE CORPORATION COMMISSION
OCT 5 X 1956
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor Graham-Michaelis Drilling Co.,
Address 1005 East Second St., Wichita, Kansas.

STATE OF KANSAS COUNTY OF SEDGWICK, ss.
W. A. Michaelis, Jr. (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God. Graham-Michaelis Drilling Co.
(Signature) W. A. Michaelis, Jr., Managing Partner.
1005 East Second St., Wichita, Kansas.
(Address)

SUBSCRIBED AND SWORN TO before me this 2nd day of October, 1956
Mary L. Barnes
Notary Public.

My commission expires 11/7/57.

PLUGGING
FILE SEC 30 T 31 R 10W
BOOK PAGE 101 LINE 16

McREYNOLDS #1

Well Record

Location: NE/4 NE/4 NW/4 Sec. 30-31S-10W
Barber County, Kansas

Commenced: August 30, 1956
Completed: September 19, 1956
(rotary)

Operator: Anschutz Drilling Co., Inc.
709 Union National Bank Building
Wichita, Kansas

Contractor: Graham-Michaelis Drilling Co.
1005 East Second Street
Wichita 1, Kansas

Casing Record: 8-5/8" @ 240' w/50 sacks cement

LOG

Sand	185
Red Bed	240
Red Bed & Shells	799
Shale & Shells	1127
Shale, Anhydrite & Lime	1933
Lime & Shale	1940
Lime	2120
Lime & Shale	2580
Brown Lime & Shale	2732
Shale & Lime	3154
Lime	3277
Lime & Shale	3760
Lime & Sand	3857
Sand	3928
Lime	4550
Chert.	4615
Chert. & Lime	4637
Chert., Lime & Shale	4691
Lime	4750
Lime & Shale	4799
Lime, Shale, & Chert.	4847
Lime	4873
Lime, Shale & Sand	4894
Core Sand	4914
Sand & Shale	4934
Shale, Sand & Chert.	4999
Lime	5030, RTD.

STATE OF KANSAS)
) ss.
COUNTY OF SEDGWICK)

RECEIVED
STATE COMMISSION
OCT 5 X 1956
CONSERVATION DIVISION
Wichita, Kansas

The undersigned, GRAHAM-MICHAELIS DRILLING COMPANY, hereby certifies that the above log is a true and correct log of the formations encountered in drilling the above well as reflected by the Daily Drilling Report.

GRAHAM-MICHAELIS DRILLING COMPANY

By John L. James
John L. James
Geologist.

Subscribed and sworn to before me
this 27th day of September, 1956.

Mary L. Burns
My commission expires: 11/7/57.

PLUGGING
FILE SEC 30 T 31 R 10W
BOOK PAGE 101 L # 16