

STATE OF KANSAS  
STATE CORPORATION COMMISSION


Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

WELL PLUGGING RECORD

BARBER County, Sec. 30 Twp. 31S Rge. 10W (E) (W)

Location as "NE/CNW/SW" or footage from lines C SW SE  
Lease Owner Sierra Petroleum Co., Inc.  
Lease Name McREYNOLDS Well No. 1  
Office Address 1015 Wichita Plaza Bldg., Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed July 4, 1965  
Application for plugging filed July 4, 1965  
Application for plugging approved July 4, 1965  
Plugging commenced July 4, 1965  
Plugging completed July 4, 1965  
Reason for abandonment of well or producing formation Dry Hole

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production \_\_\_\_\_ 19\_\_\_\_  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Archie Elving, Pratt, Kansas  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4626 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Sand & Redbed	Surface Casing	-0-	210'	8-5/8"	210'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

PLUGGED HOLE: Laid down drill pipe from 6 p.m. to 10 p.m. Filled hole with mud from T.D. to 210', put in 1/2 sk. hulls, plug and 25 sx. cement. Filled hole to 40', put in 1/2 sk. hulls, plug and 10 sx. cement. Job completed at 11:30 p.m. 7-4-65.

RECEIVED  
STATE CORPORATION COMMISSION  
JUL 9 1965  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor SIERRA PETROLEUM CO., INC.  
Address 1015 Wichita Plaza Building, Wichita, Kansas 67202

STATE OF KANSAS COUNTY OF RUSSELL, ss.

G. A. Hall

(employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

G. A. Hall, Production Superintendent  
Box 232, Russell, Kansas 67665  
(Address)

SUBSCRIBED AND SWORN to before me this 8th day of July, 1965

Notary Public.

My commission expires 10-17-67

SIERRA PETROLEUM CO., INC. - Operator

McREYNOLDS #1  
 C SW SE  
 Sec. 30-31S-10W  
 Barber County, Kansas

Elevation: 1755' DF  
 1753' GF  
 T. D. : 4626'

Commenced: 6-24-65  
 Completed: 7-4-65

Casing:  
 8-5/8" Set at 210'

Cement:  
 with 185 sx.

FORMATION

Sand & Redbed  
 Redbed  
 Salt & Shale  
 Shale & Lime  
 Lime  
 Lime & Shale  
 Lime  
 Mississippi Chert  
 Chert  
 Lime & Chert

RECEIVED  
 STATE CORPORATION COMMISSION

JUL 9 1965

CONSERVATION DIVISION  
 Wichita, Kansas

DEPTH

210  
 1325  
 1420  
 3895  
 3980  
 4040  
 4555  
 4565  
 4615  
 4626

TOPS

Herington  
 Winfield  
 Towanda  
 Ft. Riley  
 Florence  
 Council Grove  
 Admire  
 Indian Cave  
 Wabaunsee  
 Tarkio  
 Emporia  
 Elgin Zone  
 Heebner  
 Douglas Shale  
 Lansing  
 Base Kansas City  
 Mississippian

1916  
 1996  
 2064  
 2122  
 2164  
 2302  
 2678  
 2732  
 2787  
 2938  
 3003  
 3564  
 3733  
 3810  
 3924  
 4410  
 4553

STATE OF KANSAS )  
 ) ss:  
 COUNTY OF RUSSELL )

I hereby certify that the above information is true and correct to the best of my knowledge.

*G. A. Hall*  
 G. A. Hall, Prod. Supt.

My commission expires 10-17-67. Subscribed and sworn to before me this 8th day of July, 1965.

*Geroy Dietz*  
 Notary Public