

STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

Barber County, Sec. 31 Twp. 31S Rge. (E) 10 (W)

Location as "NE/CNWxSWx" or footage from lines C NW/4 SW/4

Lease Owner Quintin Little - John C. Graves

Lease Name McReynolds Well No. 1

Office Address 505 Union Center, Wichita, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed May 12 19 70

Application for plugging filed " 19 "

Application for plugging approved " 19 "

Plugging commenced " 19 "

Plugging completed " 19 "

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production " 19 "

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein

Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 4560 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	235.09	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Mudded to 220' - 1/2 sack hulls & 25 sacks cement  
Mudded to 40' - 1/2 sack hulls & 10 sacks cement  
2 sacks cement in rathole

RECEIVED  
STATE CORPORATION COMMISSION  
MAY 18 1970  
CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Graves Drilling Company, Inc.

Address 505 Union Center, Wichita, Kansas 67202

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

John C. Graves (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) John C. Graves


505 Union Center, Wichita, Kansas

(Address)

SUBSCRIBED AND SWORN TO before me this 14th day of May, 19 70

Mary Ann Scott  
Mary Ann Scott Notary Public.

My commission expires July 28, 1970



RECEIVED  
STATE CORPORATION COMMISSION  
MAY 19 1970  
CONSERVATION DIVISION  
Wichita, Kansas

ROTARY DRILLERS' LOG

OPERATOR: Quintin Little-John C. Graves DRILLING COMM: May 4, 1970  
505 Union Center  
Wichita, Kansas

CONTRACTOR: Graves Drilling Co., Inc. DRILLING COMPLETED: May 12, 1970  
505 Union Center  
Wichita, Kansas

CASING RECORD: 8 5/8" surface casing, set @ 242', w/200 sacks cement LOCATION: #1 McReynolds  
C NW SW Sec. 31-31S-10W  
Barber County, Kansas

-----  
0 - 242 Surface hole  
242 - 400 Red rock  
400 - 1115 Red bed & shale  
1115 - 1244 Shale & shells  
1244 - 1585 Shale & sandy lime  
1585 - 3680 Lime & shale  
3680 - 3684 Shale  
3684 - 3760 Lime & sandy shale  
3760 - 3862 Shale w/sandy lime  
3862 - 4352 Lime  
4352 - 4500 Lime & shale  
4500 - 4510 Chert  
4510 - 4560 Lime (Miss.)  
4560 Total Depth

I hereby certify the foregoing statements to be true and correct, to the best of my knowledge.

GRAVES DRILLING COMPANY, INC.

By *John C. Graves*  
John C. Graves

STATE OF KANSAS )  
SERGWICK COUNTY )  
Subscribed and sworn to before me, a Notary Public, this  
15th day of May, 1970.  
My Commission Expires:  
July 28, 1970

*Mary Ann Scott*  
Mary Ann Scott, Notary Public