

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barber County, Sec. 6 Twp. 31S Rge. (E) 12 (W)

Location as "NE/CNW&SW¼" or footage from lines S/2 NW/4

Lease Owner Chief Drilling Co., Inc.

Lease Name MADDIX "A" Well No. 1

Office Address Box 797 - Great Bend, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed 12/23 1965

Application for plugging filed 12/23 1965

Application for plugging approved 12/23 1965


Plugging commenced 12/23 1965

Plugging completed 12/23 1965

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well Archie Elving - Pratt, Kansas

Producing formation Depth to top Bottom Total Depth of Well 3700 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	189	8-5/8"	189	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

1/4 sack hulls & wooden plug set @ 185'
Mixed 25 sacks cement through drill pipe
1/4 sack hulls & wooden plug set @ 40'
Mixed 10 sacks cement through drill pipe
2 sacks cement in rat hole

RECEIVED
STATE CORPORATION COMMISSION
DEC 28 1965
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Chief Drilling Co., Inc.

Address Box 797 - Gt. Bend, Kansas

STATE OF KANSAS, COUNTY OF BARTON, ss.

V. Richard Hoover, President (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *Richard Hoover* CHIEF DRILLING CO., INC.

Box 797 - Gt. Bend, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of December, 1965

Carmen R. Cook
Carmen R. Cook, Notary Public.

WELL LOG

Chief Drilling Co., Inc.
Box 797
Great Bend, Kansas

MADDIX "A"
S/2 NW/4 Sec. 6-31S-12W
Barber County, Kansas

Contractor: Vaughan Drilling, Inc.

Commenced: 12-14-65
Completed: 12-23-65

Casing Record: 8-5/8" @ 189' w/150 sacks HA-5

<u>FORMATION</u>	<u>FROM</u>	<u>TO</u>	<u>ELEVATION</u>
Red Rock	0	189	1719 D.F. 1721 K.B.
Red Bed	189	1095	
Shale	1095	1558	
Shale & Lime	1558	1865	
Streaky Lime	1865	2040	
Lime & Shale	2040	2815	
Shale	2815	2930	
Shale & Lime	2930	3603	
Shale	3603	3619	
Lime	3619	3635	
Shale	3635	3663	
Sand	3663	3678	
Shale	3678	3700	
Total Depth	3700		

<u>FORMATION TOPS</u>	
Heebner	3603 -1882
Toronto	3619 -1898
Douglas Shale	3635 -1914
Douglas Sand	3663 -1942
Total Depth	3700 -1979

STATE OF KANSAS, COUNTY OF BARTON) SS

I hereby certify that the above is a true and correct copy of the Driller's Log of the well drilled in the South Half of the Northwest Quarter (S/2 NW/4) of Section 6-31S-12W, Barber County, to the best of my knowledge and belief.

CHIEF DRILLING CO., INC.

V. Richard Hoover
V. Richard Hoover, President

Subscribed and sworn to before me this 27th day of December, 1965.

Carmen R. Cook
Carmen R. Cook, Notary Public

My commission expires: Jan. 26, 1967.

RECEIVED
STATE OF KANSAS

DEC 28 1965

CONSERVATION DIVISION
STATE OF KANSAS