


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to  
Conservation Division  
State Corporation Comm.  
245 North Water  
Wichita, KS 67202



Locate well correctly on above  
Section Plot

Barber County. Sec. 6 Twp. 31S Rge. 12W E/W  
Location as "NE/CNW 1/4 SW 1/4" or footage from lines  
550' FNL & 460' FEL  
Lease Owner Texas Oil & Gas Corp.  
Lease Name Maddix "A" Well No. 5  
Office Address 200 W. Douglas-Suite 300, Wichita, KS  
Character of Well (Completed as Oil, Gas or Dry Hole) 67202  
Dry Hole  
Date Well completed February 2, 1980  
Application for plugging filed Verbal Application 19  
Application for plugging approved Verbal Approval 19  
Plugging commenced February 2, 1980  
Plugging completed February 2, 1980  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Wm. T. Owen  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well 3,026  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				10-3/4"	308'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hold. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy rotary mud from 3,026 ft. (rotary total depth) to 300 ft. Set plug at 300 ft. and cemented with 50 sacks cement. Filled hole with heavy rotary mud from 300 ft. to 40 ft. Set solid plug at 40 ft. and cemented to cellar with 20 sacks cement, 5 sacks cement in rat hole.

Plugging operations accomplished utilizing Halliburton Oil Well cementing pump truck through 4 1/2 inch drill pipe.

(If additional description is necessary, use BACK of this report)  
Name of Plugging Contractor Halliburton Services  
410 Union Center Bldg., Wichita, KS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 13 1980

STATE OF Kansas COUNTY OF Sedgwick  
Gary Younger, Agent of owner  
of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) [Signature]  
200 N. Main, Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN TO before me this 11th day of February, 1980

Elsie Willison  
Elsie Willison - Notary Public.

My commission expires July 25, 1982

KANSAS DRILLERS LOG

COMPANY Texas Oil & Gas Corp.  
FARM Maddix "A" NO. 5

SEC. 6 T. 31S R. 12W  
LOC. 550' FNL & 460' FEL

COUNTY Barber

ROTARY TOTAL DEPTH 3,026'  
COMM. January 25, 1980 COMP. February 2, 1980  
CONTRACTOR H-30, INC. (Rig #5)  
ISSUED February 11, 1980

CASING

10 3/4" Set at 308' cemented w/275 sxs cement  
8 5/8"  
5 1/2"  
4 1/2"

ELEVATION 1,833' K.F.

FIGURES INDICATE BOTTOM OF FORMATIONS

Sand and Red Bed	319'
Red Bed and Shale	1,220'
Shale and Lime	1,904'
Lime and Shale	2,144'
Shale and Lime	2,345'
Lime and Shale	2,737'
Shale and Lime	2,969'
Lime and Shale	3,026'
Rotary Total Depth	3,026'

I hereby certify the above and foregoing to be  
a true and correct log of the above described  
well as shown by the drilling reports.

H-30, INC.

*Gary Younger*  
\_\_\_\_\_  
Gary Younger

State of Kansas )  
County of Sedgwick ) ss:

Subscribed and Sworn to before me a Notary Public  
in and for said county and state this 11th day of  
February, 1980.



*Elsie Willison*  
\_\_\_\_\_  
Elsie Willison - Notary Public

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 13 1980  
CONSERVATION DIVISION  
Wichita, Kansas

My Commission Expires:  
July 25, 1982