

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission,  
800 Bitting Building,  
Wichita, Kansas

RECEIVED  
JUL 31 1936

WELL PLUGGING RECORD  
OR  
FORMATION PLUGGING RECORD

Strike out upper line  
when reporting plug-  
ging off formations.

Harper

County, Sec. 17, Twp. 35S, Rge. (E) 8 (W)

Location as "NE $\frac{1}{4}$ NW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines Center SW of NW

Lease Owner Marathon Oil Company

Lease Name Fred Zeller Well No. 1

Office Address P. O. Box 1995, Oklahoma City, Oklahoma

Character of Well (Completed as Oil, Gas or Dry Hole) Dry

Date, well completed July 22nd 1936

Application for plugging filed July 22nd 1936

Application for plugging approved July 23rd 1936

Plugging Commenced July 23rd 1936

Plugging Completed July 23rd 1936

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 193

Was permission obtained from the Conservation Division or its agents before plugging was com-  
menced? Yes

Locate well correctly on above  
Section Plat

Name of Conservation Agent who supervised plugging of this well

Producing formation Depth to top Bottom Total Depth of Well 6000 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| Formation        | Content | From | To   | Size             | Put In    | Pulled Out |
|------------------|---------|------|------|------------------|-----------|------------|
| Mississippi Lime | Water   | 4775 | 5247 | 12 $\frac{1}{2}$ | 381'-8/12 | None       |
| Viola Lime       |         | 5247 | 5320 |                  |           |            |
| Wilcox Sand      | Do.     | 5320 | 5448 | 9-5/8            | 1678'     | 1000'      |
| Silicious Lime   |         | 5535 | 6000 |                  |           |            |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used  
in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to  
feet for each plug set.

Well was circulated thru drill pipe with 11 pound rotary mud from bottom to top.  
A 4' long wooden plug was placed in hole 250 feet from top and 4 sacks cement placed  
on top of plug and filled within 20 feet of top with heavy mud, where an 8 foot wooden  
plug was placed with 12 feet of cement on top.

FILE 17-35-8W  
BOOK PAGE 54-23

(If additional description is necessary, use BACK of this sheet)

Correspondence regarding this well should be addressed to J. J. Frommer  
Address P. O. Box 1995, Oklahoma City, Oklahoma

STATE OF Kansas, COUNTY OF Harper, ss.

J. J. Frommer (employee of owner) or (owner or operator) of the above-described well,  
being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-  
described well as filed and that the same are true and correct. So help me God.

(Signature) J. J. Frommer

P. O. Box 1995, Oklahoma City, Oklahoma

(Address)

SUBSCRIBED AND SWORN to before me this 28th day of July, 1936

My commission expires March 5, 1940

16-1484

11-35-5M

Notary Public.

## FORMATION RECORD

|                             | TOP  | BOTTOM |                            | TOP  | BOTTOM  |
|-----------------------------|------|--------|----------------------------|------|---------|
| Soil and sand               | 0    | 45     | Lime (Top Kan. City) gray  | 4255 | 4428    |
| Sand and gravel gray        | 45   | 152    | Shale, blue                | 4428 | 4445    |
| Red bed and shells          | 152  | 278    | Lime, gray                 | 4445 | 4664    |
| Shale, red                  | 278  | 370    | Shale, blue                | 4664 | 4680    |
| Red bed and lime shells     | 370  | 637    | Lime, gray                 | 4680 | 4690    |
| Shale, black w/s lime       | 637  | 878    | Lime & shale, broken       | 4690 | 4725    |
| Shale, blue                 | 878  | 1050   | Shale, blue                | 4725 | 4730    |
| Shale, black w/s lime       | 1050 | 1095   | Lime & shale, broken       | 4730 | 4774    |
| Shale, blue                 | 1095 | 1112   | Lime, gray and white       | 4774 | 4852    |
| Shale, black w/s lime       | 1112 | 1195   | Sandy lime, gray           | 4852 | 4868    |
| Salt, white                 | 1195 | 1270   | Sand, brown                | 4868 | 4875    |
| Shale, black w/s salt       | 1270 | 1400   | Core                       | 4875 | 4890    |
| Lime, white                 | 1400 | 1455   | Steel line corr. on core   | 4868 | 4883    |
| Shale, blue w/s lime        | 1455 | 1495   | Sand, white                | 4883 | 4888    |
| Lime, white                 | 1495 | 1550   | Lime, gray                 | 4888 | 4915    |
| Lime w/s black shale        | 1550 | 1565   | Sandy lime, gray           | 4915 | 4926    |
| Lime, white                 | 1565 | 1675   | Free core #2               | 4926 | 4931    |
| Lime, white-shale bl. brkn. | 1675 | 1720   | Lime, gray                 | 4931 | 4977    |
| Salt, white                 | 1720 | 1745   | Sandy lime, gray           | 4977 | 4981    |
| Lime, white                 | 1745 | 1779   | Core                       | 4981 | 4987    |
| Lm. white w/s shale black   | 1779 | 1962   | Lime, gray w/s black shale | 4987 | 5007    |
| Lm. br. w/s shale black     | 1962 | 1997   | Shale, black               | 5007 | 5012    |
| Shale, blue                 | 1997 | 2040   | Lime, gray                 | 5012 | 5018    |
| Lime, white broken          | 2040 | 2060   | Sandy lime, gray           | 5018 | 5033    |
| Lime, wh. shale blk. brkn.  | 2060 | 2135   | Shale, gray                | 5033 | 5043    |
| Sandy shale, gray           | 2135 | 2165   | Sandy lime, gray           | 5043 | 5051    |
| Lm. br. w/s shale black     | 2165 | 2202   | Sand, white                | 5051 | 5068    |
| Shale w/s lime, blue        | 2202 | 2364   | Sandy lime, white          | 5068 | 5073    |
| Lm. br. w/s shale black     | 2364 | 2465   | Lime, gray                 | 5073 | 5080    |
| Shale, black                | 2465 | 2475   | Shale, gray                | 5080 | 5099    |
| Lime, white                 | 2475 | 2500   | Sandy lime, gray           | 5099 | 5118    |
| Shale, blue                 | 2500 | 2532   | Lime & stra. shale gray    | 5118 | 5133    |
| Shale, black                | 2532 | 2600   | Shale, gray                | 5133 | 5157    |
| Lime, white                 | 2600 | 2612   | Shale, black               | 5157 | 5247    |
| Shale blk. w/s lime         | 2612 | 2633   | Lm. light (Viola) gray     | 5247 | 5320    |
| Lime, white                 | 2633 | 2740   | Sand, white                | 5320 | 5322    |
| Shale, blue                 | 2740 | 2784   | Core                       | 5322 | 5326    |
| Lime, gray                  | 2784 | 2855   | Core                       | 5326 | 5332    |
| Sandy shale, black          | 2855 | 2880   | Sand, white                | 5332 | 5337    |
| Lime, gray                  | 2880 | 2985   | Core                       | 5337 | 5343    |
| Sandy shale, gray           | 2985 | 3050   | Sand, white                | 5343 | 5346    |
| Shale, blue                 | 3050 | 3060   | Shale, green               | 5346 | 5353    |
| Sandy shale, gray           | 3060 | 3091   | Core                       | 5353 | 5362    |
| Lime, white                 | 3091 | 3100   | Sand, white                | 5362 | 5380    |
| Shale, gray                 | 3100 | 3180   | Core                       | 5380 | 5398    |
| Lime, shale, gray broken    | 3180 | 3188   | Sand, blue                 | 5398 | 5419    |
| Lime, gray                  | 3188 | 3204   | Sandy lime, white          | 5419 | 5448    |
| Shale, gray                 | 3204 | 3230   | Shale, green               | 5448 | 5480    |
| Lime, gray                  | 3230 | 3249   | Lime, gray                 | 5480 | 5485    |
| Sandy lime, gray            | 3249 | 3301   | Core                       | 5485 | 5491    |
| Lime w/s black shale        | 3301 | 3326   | Shale, green w/s sand      | 5491 | 5570    |
| Shale, blue                 | 3326 | 3335   | Sandy lime, dark gray      | 5570 | 5703    |
| Lime, white                 | 3335 | 3365   | Sandy lime, light gray     | 5703 | 5896    |
| Shale, blue                 | 3365 | 3400   | Chert broken w/s lime      | 5896 | 5917    |
| Lime, gray                  | 3400 | 3485   | Chert, gray                | 5917 | 5940    |
| Shale, blue                 | 3485 | 3534   | Sandy lime, gray           | 5940 | 6000 TD |
| Lime, gray                  | 3534 | 3545   |                            |      |         |
| Sand, gray                  | 3545 | 3555   |                            |      |         |
| Sandy lime, gray            | 3555 | 3569   |                            |      |         |
| Lime, white                 | 3569 | 3580   |                            |      |         |
| Shale, blue                 | 3580 | 3590   |                            |      |         |
| Lime, white                 | 3590 | 3604   |                            |      |         |
| Sandy shale, blue           | 3604 | 3655   |                            |      |         |
| Lime, white                 | 3655 | 3685   |                            |      |         |
| Lime, gray                  | 3685 | 3699   |                            |      |         |
| Lime, white                 | 3699 | 3764   |                            |      |         |
| Lime, gray                  | 3764 | 3932   |                            |      |         |
| Sandy lime, gray            | 3932 | 3972   |                            |      |         |
| Lime, gray                  | 3972 | 3982   |                            |      |         |
| Sandy lime, gray            | 3982 | 4011   |                            |      |         |
| Lime, gray                  | 4011 | 4085   |                            |      |         |
| Shale, blue                 | 4085 | 4100   |                            |      |         |
| Sandy lime, gray            | 4100 | 4125   |                            |      |         |
| Lime, gray                  | 4125 | 4172   |                            |      |         |
| Lime, brown                 | 4172 | 4216   |                            |      |         |
| Lime, gray                  | 4216 | 4250   |                            |      |         |
| Sandy lime, gray            | 4250 | 4255   |                            |      |         |

