

KANSAS

Form CP-3
Rev. 6-4-68

12

STATE CORPORATION COMMISSION
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION
MAR 27 1978
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
245 North Water
Wichita, KS 67202

API Number 15 - 007-20575-00-00

(of this well)

Operator's Full Name Gas Producing Enterprises, Inc.
Complete Address Box 889 - St. Bend, Texas 67530
Lease Name Green Well No. 2-6
Location C-NW-SE Sec. 6 Twp 31^S Rge 27^W (E) (W) X
County Harber Total Depth 2900

Abandoned Oil Well _____ Gas Well X Input Well _____ SWD Well _____ D & A _____

Other well as hereafter indicated _____

Plugging Contractor Felso Casing Pulling

Address Box 176 - Chase, Texas 67524 License No. 683

Operation Completed: Hour 4:45 pm Day 23 Month March Year 1978

The above well was plugged as follows:

240' 8 5/8" Casing - Circ Cement - 4 1/2" Casing set @ 2858'
w/150 sack Cement - Push plug to 2825' mix & dump
4 sack Cement w/ dump bailed on top of plug Pull
2,022' 4 1/2" Casing - Bail hole down to 245' - dump
4 1/2 yard's ready mix Cement - to 35' from top of
Casing Top out when weather permitting
Pratt Ready Mix - 1111 Pratt, KS - 67124

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 3-27-78
INV. NO. 6996-W