

10 KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION AGENT'S REPORT

RECEIVED  
STATE CORPORATION COMMISSION

DEC 27 1965

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Assitant Director  
500 Insurance Building  
212 North Market  
Wichita 2, Kansas

Operator's Full Name Chief Drilling Company, Inc.

Complete Address: Box 797, Great Bend, Kansas

Lease Name Maddix "A" Well No. # 1

Location C S/2 NW Sec. 6 Twp. 31 Rge. 12 (E) (W)W

County Barber Total Depth 3700'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: \_\_\_\_\_

Plugging Contractor: Vaughan Drilling, Inc.

Address: Box 825, Great Bend, Kansas License No. \_\_\_\_\_

Operation Completed: Hour 9:00AM Day 23rd Month Dec. Year 1965

The Above well was plugged as follows:

189' of 8 5/8" surface pipe, cement circulated with 150 sacks. Fluid  
level in the hole was at 145'. 1st cementing plug and 1 sack of hulls  
was pushed in fluid to 185', and cemented with 25 sacks, through the  
drill pipe. Hole was filled with drilling mud to 40', 2nd cementing  
plug, bridged with hulls on fluid at 40', and cemented with 10 sacks  
to the base of the cellar. Rat hole bridged and cemented with 2 sacks.

I hereby certify that the above well was plugged as herein stated.

INVOICED  
DATE 12/27/65  
INV. NO. 2474-W

Signed: Arthur Elving  
Well Plugging Supervisor