

KANSAS

Form CP-3  
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 - 007 - 00656 - 00 - 00 (of this well)

Operator's Full Name Gas Producing Enterprises, Inc.  
Complete Address Box 1332 - Amarillo, Texas 79189  
Lease Name Gress Well No. 1-6  
Location Barber Sec. 6 Twp. 31<sup>N</sup> Rge. 12 (E) (W) X  
County C - SE - SE - Total Depth 3675  
Abandoned Oil Well X Gas Well X Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D & A \_\_\_\_\_  
Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Felso Casing Pulling  
Address Box 176 - Chase, Kans. 67524 License No. 683  
Operation Completed: Hour 10:15 Am Day 22 Month March Year 1978

The above well was plugged as follows:

216' - 8 5/8" Casing w/ 175 Sack Cement - 5 1/2" Casing set @ 3675'  
w/ 100 Sack Cement Prof. 3272' - 75' - Push plug to 3250'  
Mix & Dump w/ dump trailer 5 Sack Cement on top of plug  
Pull 3004' 5 1/2" Casing set 10' rock bridge from 240' to  
230' - Dump 4 yards ready mix Cement to top of Casing -

Platt Ready Mix - Pratt, Kans - 67124

RECEIVED  
STATE CORPORATION COMMISSION

I hereby certify that the above well was plugged as herein stated MAR 24 1978

INVOICED

DATE 3-24-78

INV. NO. 6990-W

Signed: [Signature]  
Well Plugging Supervisor