

15-007-00565-00-00

STATE OF KANSAS
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

BARBER County. Sec. 19 Twp. 31 Rge. (E) 12 (W)

Location as "NE/CNW/SW" or footage from lines C NW NW
Lease Owner Frontier Oil Company
Lease Name Clarke Well No. 1
Office Address Union Nat'l Bank Bldg. Wichita, Ks.
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole
Date well completed May 12, 1954
Application for plugging filed May 13, 1954
Application for plugging approved May 13, 1954
Plugging commenced May 13, 1954
Plugging completed May 13, 1954
Reason for abandonment of well or producing formation Barren

NORTH



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well _____
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 3681 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Copy of well log attached						

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Placed plug at 200' put 20 sx cement on plug, filled hole to 40' with mud, placed plug at 40', cemented to surface.

RECEIVED
STATE CORPORATION COMMISSION
MAY 19 1954
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor E. H. Adair Oil Company
Address 407 W-K-H Building, Wichita 2, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
Kenneth W. Johnson (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Kenneth W. Johnson
Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 17th day of May, 19 54
[Signature]
Notary Public.

My commission expires September 15, 1957

24-7368-S 3-53-20M
PLUGGING
FILE SEC 19 T 31 R 12W
BOOK PAGE 34 LINE 42

Company. Frontier Oil Company

Sec. 19 T 31

R 12W

CLARK

No. 1

C NW NW

Total Depth 3681'

Barber County, Kansas

Comn. 4/30/54 Comp. 5/12/54

Contractor. E. H. Adair Oil Company

Casing:

202' 8 5/8" w/ 175 sx

Elevation 1633 KB

Sand & Shale	0-160
Red Shale & Shells	160-210
Shale	210-1406
Lime	1406-1428
Shale	1428-1635
Broken Lime	1635-1688
Lime	1688-1716
Lime & Shale	1716-1840
Shale & Shells	1840-2000
Shale	2000-2060
Lime	2060-2168
Lime & Shale	2168-2209
Shale	2209-2297
Shale & Shells	2297-2480
Shale & Lime	2480-2569
Shale	2569-2913
Lime	2913-3176
Shale & Shells	3176-3395
Shale	3395-3475
Shale & Shells	3475-3534
Lime & Shale	3534-3587
Sand & Shells	3587-3600
Shale & Sand	3600-3610
Shale Sand & Shells	3610-3665
Sand & Shale	3665-3674
Sand	3674-3681

Certified Correct

[Handwritten Signature]

RECEIVED
 STATE CORPORATE COMMISSION
 MAY 27 1954
 CONSERVATION DIVISION
 Wichita, Kansas

PLUGGING
 WU SEC 19 T 31 R 12W
 BOOK PAGE 31 LINE 12