

STATE OF KANSAS  
STATE CORPORATION COMMISSION


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barber County, Sec. 21 Twp. 31 Rge. 12 (W)

Location as "NE/CNWxSWx" or footage from lines NW NW SW  
Lease Owner Aylward Drilling Company  
Lease Name Elliott "A" Well No. 1  
Office Address 813 First National Bank Building - Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed June 23 19 58  
Application for plugging filed June 23 19 58  
Application for plugging approved June 23 19 58  
Plugging commenced June 23 19 58  
Plugging completed June 23 19 58  
Reason for abandonment of well or producing formation

NORTH



Locate well correctly on above  
Section Plat

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well W. L. Lackamp - Stafford, Kansas  
Producing formation Depth to top Bottom Total Depth of Well 4326 Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	215'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Filled hole with heavy mud from total depth to 220'; Halliburton plug with 1/3 sack of hulls and 20 sacks of cement from 220' to 160'; heavy mud to 35'; Halliburton plug with 1/3 sack of hulls and 10 sacks of cement to surface.

RECEIVED  
STATE CORPORATION COMMISSION

JUL 22 1958

CONSERVATION DIVISION  
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Aylward Drilling Company  
Address 813 First National Bank Building - Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Paul W. Hesse (employee of owner) or (owner) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Paul W. Hesse  
813 1st Natl. Bank Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 26th day of June, 19 58

My commission expires December 11, 1961

Duane Jessup  
DUANE JESSUP Notary Public.

PLUGGING  
FILE SEC 21 T. 31 R. 12W  
BOOK PAGE 110 LINE 10

ELLIOTT NO. 1

Casing Record:

8 5/8" - 215'

Company: Aylward Drilling Company  
 Contractor: Aylward Drilling Company

Commenced: June 10, 1958  
 Completed: June 23, 1958

Location: NW NW SW  
 Sec. 21-31-12W  
 Barber County, Kansas

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Shale & Red Rock	0	210	Set 8 5/8" surface pipe @ 215' w/140 sacks cement.
Red Bed & Shells	210	575	
Shale & Shells	575	675	Geological Tops: (Electric Log Top)
Red Rock & Shale	675	1000	
Shale & Shells	1000	1260	Heebner 3553
Salt	1260	1420	
Shale & Lime	1420	1635	Base/Oread 3583
Lime	1635	1835	Douglas Sand 3602
Lime w/some shale	1835	2010	Lansing 3746
Lime	2010	2350	Base/Kansas City 4198
Lime & Shale	2350	3605	Mississippi 4258
Sand	3605	3684	R.T.D. 4322
Lime & Shale	3684	3770	DST 4260-4284* Open 1 hour. Weak blow thruout. Recovered 60' watery mud.
Lime	3770	4197	
Lime & Shale	4197	4264	IBHP 565#/20 min, FBHP 82#/30 min. FP 36# to 50#. *Corrected to Electric log measurements: Drillers measurements 4264-4288
Lime	4264	4288	
Cherty Lime	4288	4316	T.D. measurements: Drillers measurements 4264-4288
Lime	4316	4326	

D & A

I hereby certify that this is a true and correct copy of the above log to the best of my knowledge.

*Paul W. Lester*

Subscribed and sworn to before me this 27th day of June, 1958.

*Duane Jessup*  
 DUANE JESSUP Notary Public

My Commission expires December 11, 1961.

**RECEIVED**  
 STATE CORPORATION COMMISSION

JUL 22 1958

CONSERVATION DIVISION  
 Wichita, Kansas

<b>PLUGGING</b>	
FILE SEC	21 T. 31 R. 12W
BOOK PAGE	110 LINE 10