

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

NE SW Douglas County, Sec. 4 Twp. 13 Rge. 21 (E) 2 (W)
Location as "NE/CNW4SW4" or footage from lines 300 from south 900 west line
Lease Owner John S. Holmes INC. SE SW SW
Lease Name Lothholz Well No. 1
Office Address Eudora Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 7--9 1959
Application for plugging filed 7 6 1959
Application for plugging approved 1959
Plugging commenced 7--7 1959
Plugging completed 7 9 1959
Reason for abandonment of well or producing formation Dry Hole
If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

OIL, GAS OR WATER RECORDS

CASING RECORD

DESCRIPTION	CONTENT	FROM	TO	SIZE	PULLED IN	PULLED OUT
sand	water	820	854	8inch	540	540
				6 $\frac{1}{2}$	838	838
sand	water	965	1008	4inch	1040	1040

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

filled from 1103 to 558 with drill cuttings set rock bridge at 558 dumped 5 sacks
of cement with bailor
filled to 334 with drill cuttings and rock bridge set at 334 5 sacks of cement
dumped with bailor
filled to 234 with mud and rock bridge at 234 5 sacks of cement dumped
with bailor top of hole left for a water well
with 40 Ft. of 10 inch pipe left in hole

RECEIVED
STATE CORPORATION COMMISSION

~~JUL 16 1959~~

CONSERVATION DIVISION
sheet) Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Fred Spindle
Address 1034 E. Peoria St. Paola Kansas

STATE OF Kansas, COUNTY OF Douglas, ss.
John S Holmes (employee of owner) or (~~owner or operator~~) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature)

P O Box 58, Lawrence, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 15th day of July, 1959

My commission expires

9/24/62

V C Chase

Notary Public.

PLUGGING
FILE SEC 4 T13 R 21E
BOOK PAGE 51 LINE 20

Drilled By Fred Spindle Paola Kansas

Log of Lothholz 4-13--21 Douglas Co. Kansas

20	soil & clay	20	5	dark shale	715
19	selt	49	25	gray shale	740
16	lime	65	30	li shale	770
5	slate	70	10	dk shale	780
8	lime	78	20	sandy shale	800
14	shale	92	10	sand	810
32	lime	124	10	dk shale	820
13	shale	137	34	sand water	854
33	lime	171	10	slate	864
44	shale	215	10	li shale	874
19	lime	234	9	dk shale	893
14	shale	248	17	gr. shale	900
3	lime	251	24	sandy shale	924
3	shale	254	43	dk shale	965
8	lime	262	15	sand water	980
18	shale	280	3	slate	983
12	lime	292	25	sand water	1008
3	shale	295	14	dark shale	1022
39	lime	334	2	sand water	1024
4	shale	338	6	grey shale	1030
24	lime	362	2	dk shale	1032
3	slate	365	14	lime	1046
5	lime	370	1	shale	1047
5	shale	375	n 13	lime	1060
8	lime hertha	383	5	sand brown	1065
110	shale	493	38	lime	1103 T.D.
6	sand	499			
2	shale	501		completed 7 9 1959	
6	sand	507			
13	shale	520			
10	sandy shale	530			
5	shale	535			
11	shale	546			
7	lime	553			
11	shale	564			
4	lime	568			
21	shale	589			
3	lime	592			
5	slate	597			
7	shale	604			
8	lime	612			
13	shale	625			
6	slate	631			
7	shale	638			
2	lime	640			
30	shale sandy	670			
30	shale	700			
10	sand dry	710			

