

STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
211 No. Broadway
Wichita, Kansas

Barber County, Sec. 21 Twp. 30S Rge. (E) 11 (W)

Location as "NE/CNW/SW" or footage from lines: C NE NW

Lease Owner: Rains & Williamson Oil Co.

Lease Name: Laverentz Well No. 1

Office Address: 1425 Wichita Plaza, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole): Dry Hole

Date well completed: April 10 19 65

Application for plugging filed: April 10 19 65

Application for plugging approved: April 10 19 65


Plugging commenced: April 10 19 65

Plugging completed: April 10 19 65

Reason for abandonment of well or producing formation: No oil or gas found in commercial quantities.

If a producing well is abandoned, date of last production: - 0 - 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes



Locate well correctly on above Section Plat

Name of Conservation Agent who supervised plugging of this well: Archie Elving, Pratt, Kansas

Producing formation: Depth to top: Bottom: Total Depth of Well: 4850 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8-5/8"	261.82'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Plug & Halls to 250', set solid bridge, cement through drill pipe with 25 sacks, mud back to 40', set solid bridge, set plug with 10 sacks cement. Plug down 5 a.m. 4-10-65.

RECEIVED
STATE CORPORATION COMMISSION

APR 14 1965

CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor: Rains & Williamson Oil Co.

Address: 1425 Wichita Plaza, Wichita 2, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.

Wilson Rains

(owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Wilson Rains

1425 Wichita Plaza, Wichita 2, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 12th day of April, 19 65

My commission expires January 8, 1968

Shirley Keck Notary Public

ROTARY DRILLING LOG

Operator: Rains & Williamson Oil Co. Contractor: Rains & Williamson Oil Co.
#1 Laverentz
C NE NW Section 21-30S-11W Commenced: 3-27-65
Barber County, Kansas Completed: 4-10-65
Remarks: Set 261-82' of 8-5/8" surface casing with 200 sacks GL3 cement.

FORMATIONS:

Table with 2 columns: Formation Name and Depth (feet). Rows include Surface Soil & Sand (35'), Sand (100'), Red Bed & Shale (263'), Shale & Red Bed (885'), Anhydrite (893'), Shale & Shells (1285'), Shale & Lime Streaks (1760'), Lime & Shale (1940'), Lime (2055'), Lime & Shale (2500'), Shale (3015'), Shale & Lime (3615'), Lime & Shale (3715'), Shale & Sand (3800'), Lime & Shale (3938'), Lime (4290'), Lime & Shale (4314'), Lime (4380'), Lime, Shale & Chert (4441'), Lime & Shale (4496'), Lime (4564'), Shale (4605'), Shale & Lime (4645'), Lime (4655'), Lime & Chert (4680'), Lime (4755'), Sand & Shale (4799'), Lime (4835'), Lime & Shale (4850'), and Rotary Total Depth (D&A) (4850').

RECEIVED
STATE CORPORATION COMMISSION

APR 14 1965

CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
Wilson Rains, Partner

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 12th day of April, 1965.

My Commission Expires:
January 8, 1968

Shirley Keck
Shirley Keck, Notary Public