


STATE OF KANSAS
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
508 Bittling Building
Wichita, Kansas

Barber County, Sec 17 Twp 34S Rge (E) 13(W)
Location as "NE/CNW $\frac{1}{4}$ SW $\frac{1}{4}$ " or footage from lines SW $\frac{1}{4}$ SE $\frac{1}{4}$ SW $\frac{1}{4}$
Lease Owner Aylward Drilling Company et al
Lease Name Blunk Well No. 1
Office Address 813 First National Bank Bldg.; Wichita, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry
Date well completed August 20 1952
Application for plugging filed August 20 1952
Application for plugging approved August 21 1952
Plugging commenced August 20 1952
Plugging completed August 20 1952
Reason for abandonment of well or producing formation Dry



If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives - Pratt, Kansas
Producing formation Depth to top Bottom Total Depth of Well 5250 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled Out
				8 5/8"	214'	None

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Pushed Plug to 200' with drill pipe and put 20 sacks cement on top of plug through drill pipe. Pulled drill pipe and bridged hole at 30 feet; bridge held joint of drill pipe. Put 10 sacks of cement on top of bridge, cement came to bottom of cellar.

4-3-52


(If additional description is necessary, use BACK of this sheet)
Correspondence regarding this well should be addressed to Aylward Drilling Company
Address 813 First National Bank Building; Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.
N. W. Aylward (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) *N. W. Aylward*
410 E. 4th; Hoisington, Kansas (Address)

SUBSCRIBED AND SWORN to before me this 2nd day of September 1952
Alfred J. Shalshy Notary Public

My commission expires July 9, 1956



BLUNK #1

Casing Record:
8 5/8" - 214'

Company: Aylward Drilling Company et al
Contractor: Aylward Drilling Company

Commenced: July 21, 1952
Completed: August 20, 1952

Description
SW SE SW Sec. 17-34-13W
Barber County, Kansas

Elevation: 1620' D.F.
1618' Gr.

Dry and Abandoned

	<u>From</u>	<u>To</u>	<u>Remarks</u>
Red Clay	0	40	Set 214' 8 5/8", cemented with 105 sacks cement.
Redbed	40	450	
Redbed & Sand	450	830	
Redbed & Lime Streaks	830	1080	
Redbed & Shales	1080	1145	
Anhydrite & Shale	1145	1240	
Blue Shale & Shells	1240	1330	
Salt & Sand & Shale	1330	1790	
Lime & Shale	1790	2080	
Hard Sandy Lime	2080	2210	
Lime & Shale	2210	2305	
Lime	2305	2470	
Lime & Shale	2470	3180	
Lime	3180	3260	
Blue Shale	3260	3280	
Lime & Shale	3280	3370	
Shale Blue and Gray	3370	3415	
Shale & Lime	3415	3815	
Sandy Lime & Shale	3815	3870	
Shale & Lime	3870	4100	
Lime	4100	4145	
Lime Chalky	4145	4190	
Lime	4190	4507	
Lime & Shale	4507	4625	
Lime	4625	4710	
Lime & Shale	4710	4710	
Lime	4710	4810	
Shale & Lime	4810	4820	
Lime	4820	4858	
Lime & Shale	4858	5073	
Lime	5073	5074	
Shale & Lime	5074	5111	
Lime	5111	5125	
Lime & Chirt	5125	5152	
Lime	5152	5166	
Chirty Lime	5166	5191	
Shale & Lime	5191	5208	
Shale Lime Hard Sand	5208	5230	
Sand	5230	5250	Total Depth

STATE OF KANSAS
SEP 3 1952
CONSERVATION DIVISION
Wichita, Kansas

I certify that this is a true and correct copy of the above log to the best of my knowledge.

A. Skalsky
A. Skalsky

Subscribed and sworn to before me this 21st day of August, 1952.

Flavene Cooper
Flavene Cooper
Notary Public

My commission expires:
July 16, 1956.

PLUGGING
FILE SEC 17-34-13W
BOOK PAGE 38 LINE 4v