


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

WELL PLUGGING RECORD

NORTH



Locate well correctly on above
Section Plat

Barber County. Sec. 15 Twp. 34 Rge. 13 (X) (W)

Location as "NE/CNW/SW" or footage from lines SE SW NE

Lease Owner The Palmer Oil Corporation

Lease Name Schubach Well No. 1

Office Address 415 Union National Bank Building, Wichita 2, Kansas

Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole

Date well completed June 16, 1953

Application for plugging filed June 16, 1953

Application for plugging approved June 16, 1953

Plugging commenced June 16, 1953

Plugging completed June 16, 1953

Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19

Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives

Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 5330 Feet

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8"	247'	None
				5 1/2"	5330	4167' 10"

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Filled with chat to 4490. Run 5 sacks cement with Dump Bailer.
Mudded hole to 240' - set rock bridge and run 20 sacks cement.
Mud to 35' - set rock bridge cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Forbes Casing Pulling Co.

Address Great Bend, Kansas

STATE OF KANSAS, COUNTY OF SEDGWICK

Edgar E. Smith ^{ss.} employee of owner of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Edgar E. Smith
Union National Bank Bldg., Wichita, Kansas
(Address)

SUBSCRIBED AND SWORN TO before me this 4th day of August, 1953.

My commission expires July 23, 1955.

Irvin Meyer
Notary Public.

RECEIVED
STATE CORPORATION COMMISSION

AUG - 5 1953
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC. 15 T 37 R 19 W
BOOK PAGE 105 LINE 29

WELL LOG - SCHUPBACH #1

WELL OWNER: The Palmer Oil Corporation

Location: SE SW NE
Section 15-34S-13W
Barber County, Kansas
Elevation: 1574 R.B.

CONTRACTOR: The Palmer Oil Corporation

Commenced: 4/8/53

Completed: 6/16/53

RESULTS: Dry Hole

Casing Record

Figures Indicate Bottom of Formations

8 5/8" - 247' cemented w/ 175 sx.

Shale & shells	247
Red bed & shale	480
Red bed, shale & shells	1365
Shale & shells	1480
Anhydrite	1560
Shale & shells	1885
Lime & shale	2410
Lime	2510
Lime & shale	3215
Lime	3273
Lime & shale	4161
Lime	4546
Lime & shale	4619
Lime	4778
Cherty lime	4803
Lime	4841
Lime & shale	4865
Lime	4980
Shale & lime	5022
Lime	5159
Shale & lime	5183
Lime	5234
Sand & shale	5303
Arbuckle	5330 R. T. D.

Formation Tops (R. B.)

Elgin Sand	3743
Douglas Shale	3864
Douglas Sand	3920
Lansing	4047
Mississippi	4660
Kinderhook	4845
Chattanooga	4971
Misener	5024
Viola	5037
Simpson Shale	5143
Simpson Sand	5174
Arbuckle	5301
R. T. D.	5330

This is to certify that the above is a true and correct log, according to the daily drilling reports.

THE PALMER OIL CORPORATION

By Edgar E. Smith

STATE OF KANSAS)
) ss:
SEDGWICK COUNTY)

Subscribed and sworn to before me, a Notary Public, in and for said County and State, this 4th day of August, 1953.

My Commission Expires: July 23, 1955.

Luis Meyer
Notary Public
RECEIVED
STATE CORPORATION COMMISSION
AUG - 5 1953
CONSERVATION DIVISION
Wichita, Kansas

PLUGGING
FILE SEC 15 T 34 R 130
BOOK PAGE 105 LINE 39