


STATE OF KANSAS  
STATE CORPORATION COMMISSION

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
211 No. Broadway  
Wichita, Kansas

Barber County. Sec. 9 Twp. 31S Rge. 10W (E) (W)

Location as "NE/CNW/SW" or footage from lines NE NW NE  
Lease Owner K & E Drilling, Inc.  
Lease Name Morisse Well No. #1  
Office Address 1006 Central Bldg., Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) dry hole  
Date well completed February 5, 1956 19  
Application for plugging filed February 5, 1956 19  
Application for plugging approved February 5, 1956 19  
Plugging commenced February 6, 1956 19  
Plugging completed February 6, 1956 19



Locate well correctly on above  
Section Plat

Reason for abandonment of well or producing formation commercial quantities of oil not found  
If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? yes

Name of Conservation Agent who supervised plugging of this well M. A. Rives  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	306'	none

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 300'. Set solid bridge at 300!  
Put in 20 sacks cement through drill pipe and heavy mud to 35'  
Set solid bridge at 35' and capped with 10 sacks cement

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor K & E DRILLING, INC.  
Address 1006 Central Bldg., Wichita, Kansas

STATE OF Kansas, COUNTY OF Sedgwick, ss.  
Dale Silcott (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Dale Silcott  
1006 Central Bldg., Wichita, Kansas  
(Address)

SUBSCRIBED AND SWORN TO before me this 9th day of February, 19 56

My commission expires June 25, 1956

James Mader Notary Public.

PLUGGING  
FILE SEC 9 T 31 R 10W  
BOOK PAGE 37 LINE 11

RECEIVED  
FEB 10 1956  
2-10-56  
CONSERVATION DIVISION  
Wichita, Kansas



K & E DRILLING, INC.  
Morisse #1

NE NW NE Sec. 9-31S-10W  
Barber County, Kansas

Comm: 1-18-56  
Comp: 2-5-56  
Total Depth: RTD 4946'

Casing                      Cement  
8 5/8" Set @ 306              225 sacks

<u>FORMATION</u>	<u>DEPTH</u>
Sand	0- 170
Red shale	170- 280
Red bed	280- 306
Shale & shells	306- 1438
Anhydrite	1438- 1450
Shale-shells	1450- 1730
Lime	1730- 2065
Lime-shale	2065- 2220
Lime	2220- 2335
Lime-shale	2335- 3085
Lime	3085- 3463
Lime & shale	3463- 3590
Lime & shale	3590- 3765
Sand & shale	3765- 3835
Sand	3835- 3868
Lime (Kan-K.C.)	3868-3915
Lime	3915- 4499
Mississippi	4499- 4597
Lime	4597- 4638
Shale	4638- 4728
Lime (Viola)	4728- 4800
Shale & lime	4800- 4808
Simpson	4808- 4870
Shale - Lime	4870- 4920
Arbuckle Lime	4920- 4946 $\frac{1}{2}$

STATE OF KANSAS )  
                          )     SS  
SEDGWICK COUNTY )

I hereby certify that the above information is true and correct to the best of my knowledge.

  
\_\_\_\_\_

Subscribed and sworn to before me this 7th day of February, 1956.

  
\_\_\_\_\_  
Notary Public

My commission expires: June 25, 1956

**PLUGGING**  
FILE SEC 9-T-31-R-10W  
BOOK PAGE 37 LINE 11

FEB 10 1956  
CONSERVATION DIVISION  
Wichita, Kansas