

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

## State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

AUG 8 1966

CONSERVATION DIVISION  
Wichita, Kansas

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Dear Sir:

Mr. Curley Brau of Edmiston Drilling Co. Inc. has this date requested permission to plug the following described well:

Mr. Brau guarantees payment of the plugging fee.

Operator's full Name: E. K. Edmiston

Complete Address: 425 First National Bank Bldg., Wichita, Ks.

Lease Name: Massoni Well No. # 1

Location: C SE NE Sec. 24 Twp. 30 Rge. 11 (E)(W) W

County Barber Total Depth 4800' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Brau was instructed to plug the well as follows:

244' of 8 5/8" surface pipe, cement circulated with 175 sacks. Fill hole with drilling mud to 240', 1st cementing plug, bridge with 1/2 sack of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40', 2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10 sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Archie Elving  
Conservation Division Agent