

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

JAN 2 1963

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

December 20, 1962

CONSERVATION DIVISION
 Wichita, Kansas

Dear Sir:

Mr. Woodie Gray of Viersen & Cochran has this
 date requested permission to plug the following described well:

Mr. Woodie Gray guarantees payment of the plugging fee.

Operator's full Name: Viersen & Cochran

Complete Address: P.O. Box 280 Okmulgee, Oklahoma

Lease Name: C.D. Williams Well No. 1

Location: Center Lot 3 Sec. 15 Twp. 35 Rge. 5 (E) (W) X

County Harper Total Depth 4040 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Woodie Gray was instructed to plug the well as follows:

270' of 8 5/8" surface pipe circulated with cement. Hole
filled to 150' with heavy drill mud, 10' rock bridge and
20 sacks cement. Hole filled to 40' with heavy drill mud,
10' rock bridge and 10 sacks cement to base of cellar.

Very truly yours,

W. J. Justice
 Conservation Division Agent