

15-077-20045-00-00

State of Kansas



WM. H. AVERY Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
HARRY G. WILES Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 11 1968  
CONSERVATION DIVISION  
Wichita, Kansas

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita 2, Kansas

Intent to Drill,  
filed December 26, 1967.

Dear Sir:

Mr. Dale Buller of Gabbert-Jones, Inc. has this  
date requested permission to plug the following described well:

Mr. Buller guarantees payment of the plugging fee.

Operator's full Name: Parley Oil Company

Complete Address: P. O. Box 14371, Oklahoma City, Oklahoma

Lease Name: Sapphire Well No. # 1

Location: C NW NW Sec. 15 Twp. 35 Rge. 6 (E)(W) W

County Harper Total Depth 4070' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Buller was instructed to plug the well as follows:

247' of 8 5/8" surface pipe, cement circulated with 225 sacks. Fill  
hole with drilling mud to 240', 2nd cementing plug, bridge with 1/2 sack  
of hulls, and cement with 25 sacks. Fill hole with drilling mud to 40',  
2nd cementing plug, bridge with 1/2 sack of hulls, and cement with 10  
sacks to base of cellar. Bridge and cement rat hole with 2 sacks.

Very truly yours,

Arlie Elving  
Conservation Division Agent