

State of Kansas



FORM - CP-2

JOHN ANDERSON, Jr. Governor
 RICHARD C. BYRD Chairman
 ALVIN F. GRAUERHOLZ Commissioner
 HARRY G. WILES Commissioner
 RAYMOND B. HARVEY Secretary
 CHARLES C. McCARTER Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS

VERBAL PERMIT FORM
 (To Be Filed By Plugging Agent)

RECEIVED
 STATE CORPORATION COMMISSION

SEP 23 1963

CONSERVATION DIVISION
 Wichita, Kansas

J. P. Roberts
 Assistant Director
 500 Insurance Building
 212 North Market
 Wichita 2, Kansas

Dear Sir:

Mr. Joe Verzey of Kewanee Oil Co. has this

date requested permission to plug the following described well:

Mr. Verzey guarantees payment of the plugging fee.

Operator's full Name: Kewanee Oil Co.

Complete Address: Box 2093, Wichita, Kansas

Lease Name: Miller Well No. # 1

Location: C SW NE Sec. 8 Twp. 35 Rge. 6 (E) (W) #

County Harper Total Depth 5200 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Verzey was instructed to plug the well as follows:

488' of 8 5/8" surface pipe, cemented to top.

Fill hole with mud to 480', 1st cementing plug, cemented

with 20 sacks. Fill hole with mud to 285', 2nd cementing

plug, cement with 20 sacks. Fill hole with mud to 30',

3rd cementing plug, cement with 8 sacks to base cellar.

These plugging orders were given by Eldon Petty, Hays, Ks.
 Very truly yours,

Archie Elving
 Conservation Division Agent