

State of Kansas



FORM - CP-2

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSASVERBAL PERMIT FORM
(To Be Filed By Plugging Agent)RECEIVED
STATE CORPORATION COMMISSION

MAY 25 1964

CONSERVATION DIVISION
Wichita, KansasJ. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

Mr. Bill Musgrove of Bowers Drilling Co., Inc. has this
date requested permission to plug the following described well:Mr. Musgrove guarantees payment of the plugging fee.Operator's full Name: Kern-Landes Exploration Co., Inc.Complete Address: Box 107, Liberal, KansasLease Name: Schrock Well No. # 1Location: C SE NW Sec. 4 Twp. 35 Rge. 6 (E) (W) WCounty Harper Total Depth 4080 Oil Well Gas Well Input Well SWD Well D & A X Lost Hole Mr. Musgrove was instructed to plug the well as follows:

265' of 8 5/8" surface pipe, cemented with 200 sacks. Fill
hole with drilling mud to 260', 1st cementing plug, bridge
with hulls, and cement with 25 sacks. Fill hole with drill-
ing mud to 40', 2nd cementing plug, bridge with hulls, and
cemented with 10 sacks to base cellar. Bridge and cement rat
with 2 sacks.

Very truly yours,

Conservation Division Agent