

CRZ

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
AUG 27 1973
8-27-73
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Damme of Red Tiger Drlg Co has this

date requested permission to plug the following described well:

Mr. Damme guarantees payment of the plugging fee.

Operator's full Name: Smith & Fancher

Complete Address: 330 Magestic Bldg Denver, CO

Lease Name: Exline AXLINE Well No. 1

Location: C SE Sec. 5 Twp. 31 Rge. 11 (E)(W) W

County: Barber Total Depth 3874 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Damme was instructed to plug the well as follows:

308 ft 8 5/8 surface cemented with 225 sacks. Fill hole
to 260 ft, plug, 1/2 sack hulls, 25 sacks cement. Mud to
40 ft, plug, 1/2 sack hulls, 10 sacks cement to surface.
2 sacks cement in rat hole.

Very truly yours,

Russell E. ...
Conservation Division Agent