

To: 1 040621
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
290 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

2-14 API NUMBER 15-007-22,350-00-00 98p
N/2 SW NE, SEC. 36, T. 30 S, R. 12 W/E

TECHNICIAN'S PLUGGING REPORT

Operator License # 5123
Operator: Pickrell Drilling Company, Inc.
Name & Address: 110 N. Market, Suite 205
Wichita, KS 67202

3630 feet from S section line
1980 feet from E section line
Lease Name Thom Well # A-1
County Barber 143.58
Well Total Depth 4418 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 270

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____
Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105
Address P.O. Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 9 a.m. Day: 14 Month: 2 Year: 19 92

Plugging proposal received from Don Aumiller
(company name) Pickrell Drilling Company, Inc. (phone) 316-532-3511

were: 4 1/2" at 4417' w/150 sx cement, PBD 4386', Perfs at 4300-12'
1st plug sand back to 4250' and dump 4 sx cement on top of sand through bailer,
2nd plug pump 3 sx hulls, 10 sx gel, 60 sx cement, 10 sx gel, 1 sx hulls, released 8 5/8"
wiper plug and pumped 125 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____
Operations Completed: Hour: 9:45 a.m. Day: 14 Month: 2 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug sanded back to 4250' and dumped 4 sx cement on top of
sand bridge through bailer,
2nd plug pumped down 8 5/8" surface pipe with 300 lbs. hulls, 10 sx gel, 60 sx cement,
10 sx gel, 100 lbs. hulls, released 8 5/8" wiper plug and pumped 120 sx cement.
Maximum pressure 800 psi and shut in 150 psi.

RECEIVED
STATE CORPORATION COMMISSION
FEB 19 1992
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Used common cement by Allied. Recovered 3400' of 4 1/2" casing.
(If additional description is necessary, use BACK of this form.)

INVOICED

(If additional description is necessary, use BACK of this form.)
observe this plugging.

DATE 2-27-92
C.M. NO. 34660

Signed Stephen J. Pfeiffer (TECHNICIAN)