

1 010099

API NUMBER 15- 007-20,817-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW SE NW, SEC. 36, T 30 S, R 12 (W/E)

2970 feet from S section line

3630 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name Thom "C" Well # 1

Operator: TXO Production Corporation  
Name & Address: 155 N. Market, Suite 1000  
Wichita, KS 67202

County Barber

Well Total Depth 4275 138.94 feet

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 10 3/4 feet 253

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service License Number 5893

Address P. O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 3:00 pm Day: 28 Month: February Year: 19 86

Plugging proposal received from Jerry Pritchert

(company name) TXO (phone) 316-269-7600

were: 4 1/2" at 4256' PBTD 4275' Open Hole

1st plug sand back to 4120' and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, release 10 3/4" rubber plug and pump 180 sx cement.

Plugging Proposal Received by Paul A. Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4:00 pm Day: 28 Month: February Year: 19 86

ACTUAL PLUGGING REPORT 1st plug sanded back to 4120' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 2 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls, released 10 3/4" rubber plug and pumped 180 sx cement.

Maximum pressure 600 psi and shut in 600 psi

Remarks: Used 50/50 Pozmix 2% gel by DS Services. Recovered 3052' 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

INVOICED

RECEIVED STATE CORPORATION COMMISSION

DATE MAR 12 1986

MAR 11 1986

Signed

*Paul A. Luthi*  
(TECHNICIAN)

CONSERVATION DIVISION  
Wichita, Kansas

FORM CP-2/3  
Rev. 01-84

INV. NO. 12967  
2-28