

2 040399

12-4-87

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 077-20,761-00-00

SE SE SE, SEC. 5, T 35 S, R 6 W/EX

330 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5171

Lease Name KU Endowment Well # 1

Operator: TXO Production Corporation

County Harper 171.44

Name & Address 155 N. Market, Suite 1000

Well Total Depth 5275 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 264

Abandoned Oil Well Gas Well Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pulling License Number 5105

Address Great Bend, KS 67530

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Mike

(company name) Great Bend Casing Pulling (phone)

were: 4 1/2" @ 4149 Perfs @ 3682-84, 3676-78

50 sxs on bottom 3 sxs hulls, 15 sxs gel, 100 sxs cement

Plugging Proposal Received by District #2 Office
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None

Operations Completed: Hour: 11:00 Day: 4 Month: 12 Year: 1987

ACTUAL PLUGGING REPORT The perfs were shut off by pumping 50 sxs common cement to

3600'. The 4 1/2" was shot off and recovered from 2480'. The top was squeeze

plugged by pumping 3 sxs hulls, 15 sxs gel, 100 sxs 60/40 poz, 2% gel.

RECEIVED
STATE CORPORATION COMMISSION

MAR 21 1988

Remarks: B. J. Titan Max 900# Shut in 400#

(If additional description is necessary, use BACK of this form) CONSERVATION DIVISION
Wichita, Kansas

INVOICED
did not observe this plugging.

DATE 3-2-88

Signed [Signature] (TECHNICIAN)

INV. NO. 20212