

1 041215

To: STATE CORPORATION COMMISSION
Wichita State Office Bldg. - PLUGGING SECTION
130 S. Market, Room 2078
Wichita, KS 67202

API NUMBER 15-007-22,522 -0000

NE SE SW, SEC. 5, T 31 S, R 11 WEX
990 feet from S section line
2310 feet from WEX section line

10-23

TECHNICIAN'S PLUGGING REPORT
Operator License # 5046
Operator: Raymond Oil Co., Inc.
Name: P.O. Box 48788
Address: Wichita, KS 67201

Lease Name Cargill Well # I
County Barber 14852
Well Total Depth 4570 feet
Conductor Pipe: Size feet
Surface Casing: Size 8 5/8 feet 257

Abandoned Oil Well Gas Well Input Well SWD Well D&A X
Other well as hereinafter indicated

Plugging Contractor Duke Drilling Co., Inc. License Number 5929
Address 310 W. Central, Wichita, KS 67202

Company to plug at: Hour: 11:30 a.m. Day: 23 Month: 10 Year: 19 96

Plugging proposal received from John Armbruster
(company name) Duke Drilling Co. (phone) 316-267-1331

Work: to fill hole with heavy mud and spot cement through drill pipe
1st plug at 600' with 50 sx cement, 2nd plug at 275' with 40 sx cement,
3rd plug at 40' with 10 sx cement, 4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement,
Fill water well with 10 sx cement.

Plugging Proposal Received by Stephen J. Pfeifer
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 12:45 p.m. Day: 23 Month: 10 Year: 19 96

ACTUAL PLUGGING REPORT 1st plug at 600' with 50 sx cement,
2nd plug at 275' with 40 sx cement,
3rd plug at 40' with 10 sx cement,
4th plug to circulate rathole with 15 sx cement,
5th plug to circulate mousehole with 10 sx cement,
Water well filled with 10 sx cement.

Remarks: Used 60/40 Pozmix 6% gel by United.
(if additional description is necessary, use BACK of this form.)

RECEIVED
KANSAS CORP COM
OCT 28 P 4:24
10-28-96

INVOICED

DATE OCT 30 1996

INV. NO. 468538

10-23

Signed Stephen J. Pfeifer
(TECHNICIAN)

9-29-96

EFFECTIVE DATE: DISTRICT # 5547

Must be approved by the K.C.C. five (5) days prior to commencing well

Expected Spud Date 10-6-96

Spot NE... SE... SW... sec 5... Twp 31 S, Rg 11... East

OPERATOR: License # 5046 Name: Raymond Oil Co., Inc. Address: P.O. Box 48788 City/State/Zip: Wichita, KS 67201 Contact Person: Pat Raymond Phone: 316-2674214

990 feet from South North line of section 2310 feet from East/West line of section IS SECTION XX REGULAR IRREGULAR (NOTE: Locate well on the section plat on Reverse Side) County: Barber Lease Name: Carroll Well #: 1 Field Name: Wildcat

CONTRACTOR: License #: 5929 Name: Duke Drig. Co.

Well Drilled For: Well Class: Type Equipment:

XX Oil ... Enh Rac ... Infield ... Mud Rotary XX Gas ... Storage ... Pool Ext. ... Air Rotary ... OWD ... Disposal ... Wildcat ... Cable ... Seismic: # of Holes ... Other ... Operator: old well information as follows: Well Name: Coop. Date: Old Total Depth

Length of Surface Pipe Planned to be set: 250 Length of conductor pipe required: 4500 Projected Total Depth: 4500 Formation at Total Depth: Mississippi Water Source for Drilling Operations: well farm pond other

Directional, Deviated or Horizontal wellbore? If yes, true vertical depth: Bottom Hole Location: Exp. 3/24/97

DNR Permit #: Will Cores Be Taken? If yes, proposed zone: 200' Alt. Reg.

The undersigned hereby affirms that the drilling, completion and eventual plugging of this well will comply with K.S.A. 55-101, et. seq.

Rig 2 793-0841

John Armbuster

Pusher SPUD DATE 10-16-96 INIT. 210

LENGTH SURFACE PLANNED 250+

RESERVE PIT STATUS- REMOVE FLUID LINED after salt sect. bbls. when done bbls.

RATHOLED AHEAD? Y N SIZE HOLE SURFACE PIPE 8 7/8 @ 257 CONDUCTOR ANHYDRITE T- B- ELEVATION

TD 4570 FORMATION Kinderhook (Miss.)

RAN PIPE @ DV TOOL ALT II DONE SX Y N

Arbuckle Plug @ Ft. W/ SX Bug./Council @ Ft. W/ SX Anhydrite Base @ 600 Ft. W/ 50 SX 1/2 Base Anyh. @ Ft. W/ SX 1/2, 1/2 Plug @ Ft. W/ SX Bottom Surface @ 275 Ft. W/ 40 SX 40' Plug @ 40 Ft. W/ 10 SX

EAT HOLE CIRC/W 15 SX MOUSE HOLE W/ 10 SX

WATER WELL 10 SX (Irr. Well Pond Hauling)

TECHNICIAN SP DATE 10-23-96

TYPE OF CEMENT 60/40 2026

STARTING TIME 11:30 (AM/PM) DATE 10/23

COMPLETION TIME 12:45 (AM/PM) DATE 10/23

EMENT COMPANY United

RECEIVED OCT 28 1996 ANAS CORP COM