

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-007-20668-00-02
Spot: SWSWSW Sec/Twnshp/Rge: 4-31S-12W
2180 feet from N Section Line, 330 feet from W Section Line
Lease/Unit Name: OLSON 1-4 Well Number: OWWO
County: BARBER Total Vertical Depth: 3890 feet

Operator License No.: 31434
Op Name: L & J OIL PROPERTIES, INC.
Address: 635 N. STRATFORD
WICHITA, KS 67206

Conductor Pipe: Size feet: \$126.43
Surface Casing: Size 8.625 feet: 270 WITH 225 SX CMT
Production: Size 4.5 feet: 3888 WITH 125 SX CMT
Liner: Size feet:

Well Type: GAS UIC Docket No: Date/Time to Plug: 11/27/2002 3:10 PM
Plug Co. License No.: 5105 Plug Co. Name: CLARKE CORPORATION
Proposal Rcvd. from: ALAN VRATIL Company: CLARKE CORPORATION Phone: (620) 886-5665

Proposed Plugging Method: SET CIBP @ 3760' WITH 2 SX CMT. 1ST PLUG AT 600' WITH 50 SX CMT. 2ND PLUG AT 300' WITH 50 SX CMT. 3RD PLUG AT 40' WITH 10 SX CMT.

Plugging Proposal Received By: KEVIN STRUBE WitnessType: Plugging Operations 100% Witnessed (Complete)
Date/Time Plugging Completed: 11/27/2002 4:30 PM KCC Agent: SCOTT ALBERG

Actual Plugging Report:


PBTD 3840'. PERFS AT 3816-3820'. CIBP @ 3750' WITH 2 SX CMT ON TOP WITH BAILER. 1ST PLUG PUMP 10 SX GEL & 50 SX CMT AT 600'. 2ND PLUG PULL TO 300' & PUMP 50 SX CMT. 3RD PLUG AT 0-40' WITH 10 SX CMT.

RECEIVED
DEC 05 2002
KCC WICHITA

Remarks: USED 60/40 POZMIX 6% GEL BY ALLIED. RECOVERED 2470' OF 4 1/2" CASING.

Plugged through: CSG

District: 01



Signed

[Signature]
(TECHNICIAN)

INVOICEL
DATE 12-5-02
WV. NO. 2003060915