

To: 1 060148  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

10-29 API NUMBER 15-007-22,407-00-00 318R

NE SW NE, SEC. 2, T. 30 S, R. 11 W/EK  
1650 feet from N section line  
1650 feet from E section line

TECHNICIAN'S PLUGGING REPORT  
Operator License # 5046  
Operator: Raymond Oil Company, Inc.  
Name & Address: P.O. Box 48788  
Wichita, KS 67201

Lease Name Van Ranken Well # 1  
County Barber 94.84  
Well Total Depth 2918 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 262

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Trans Pac Drilling License Number 5841

Address 1000 One Main Pl., Wichita, KS 67202

Company to plug at: Hour: 7 a.m. Day: 29 Month: 10 Year: 19 92

Plugging proposal received from Gary Pugh

(company name) Trans Pac Drilling (phone) 316-265-0226

were: to fill hole with heavy mud and spot cement through drill pipe

1st plug at 1175' with 50 sx cement, 2nd plug at 300' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

Plugging Proposal Received by Case Morris (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 9:30 a.m. Day: 29 Month: 10 Year: 19 92

ACTUAL PLUGGING REPORT 1st plug at 1175' with 50 sx cement,

2nd plug at 300' with 50 sx cement,

3rd plug at 40' with 10 sx cement,

4th plug to circulate rathole with 15 sx cement,

5th plug to circulate mousehole with 10 sx cement.

RECEIVED STATE CORPORATION COMMISSION

OCT 30 1992

Remarks: Used 60/40 Pozmix 6% gel by B.J. Services.

(If additional description is necessary, use BACK of this form.)

INVOICED I did not observe this plugging.

DATE 11-20-92

Signed Case Morris (TECHNICIAN)

WV. NO. 36838

10-29-92 JAN 22 1993