

1 030451

R

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 007-20,467-00-00

SE NW NW, SEC. 10, T 30 S, R 11 W/X

4280 feet from S section line

4280 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5047

Lease Name Hirsch Well # 1

Operator: Rupe Oil Company

County Barber 95.26

Name & Address Box 2273

Well Total Depth 2931 feet

Wichita, KS 67201

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 261

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Gallagher Well Service, Inc. License Number 8752

Address Box 100, Isabel, KS 67065

Company to plug at: Hour: 11:40 am Day: 19 Month: June Year: 19 85

Plugging proposal received from John Gallagher

(company name) Gallagher (phone) 316-739-4564

were: 4 1/2" at 2833' Perfs at 2730' 34'

1st plug pump 2 sx hulls and 25 sx cement to bottom

2nd plug squeeze well with 1 sack hulls, 10 sx gel, 50 sx cement, 5 sx gel, 1 sack hulls, release 8 5/8" rubber plug and pump 100 sx cement.

Plugging Proposal Received by Steve Durrant (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 12:20 pm Day: 19 Month: June Year: 19 85

ACTUAL PLUGGING REPORT 1st plug pumped 2 sx hulls and 25 sx cement to bottom, 2nd plug squeezed well with 1 sack hulls, 10 sx gel, 50 sx cement, 5 sx gel, 1 sack hulls, released 8 5/8" rubber plug and pumped 100 sx cement.

RECEIVED STATE CORPORATION COMMISSION

JUL 01 1985

CONSERVATION DIVISION Wichita, Kansas

Maximum pressure 600 psi and shut in 500 psi

Remarks: Used 60/40 Pozmix 6% gel by Halliburton Rec' 1400' 4 1/2" (if additional description is necessary, use BACK of this form.)

Jack Luthi observed this plugging (if not observed, observe this plugging.)

INVOICED DATE 7-10-85 INV. NO. 8830

Signed Steve Durrant (TECHNICIAN)