

1 040394

1-9 15-007-01030-00-02

145  
R

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drilled 1946

SW SW SE, SEC. 19, T 30 S, R 11 W/E  
330 feet from S section line  
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5893

Lease Name Wulf Well # A-2

Operator: Pratt Well Service, Inc.  
Name & Address P.O. Box 847  
Pratt, KS 67124

County Barber 149.18  
Well Total Depth 4590 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 feet 240

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 3:30 p.m. Day: 9 Month: 1 Year: 1990

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service, Inc. (phone) 316-672-2531

were: 4 1/2" @ ? Perfs at 4428-38'

1st plug sand back to 4378' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 100 sx cement.

Plugging Proposal Received by Case Morris  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 4 p.m. Day: 9 Month: 1 Year: 1990

ACTUAL PLUGGING REPORT 12/1/89-Duane Rankin witnessed- Pumped down 8 5/8" with 350 lbs. hulls,  
10 sx gel, 50 sx cement, and 6-8 sx gel. Cement circulated on backside. 60/40 Poz 6% gel.

1/9/90 Pratt Well Service washed hole back down to good cement at 158', circulated hole  
from 158' to surface with 40 sx of cement. Cement circulated through 2 3/8" tubing.

Remarks: Used 60/40 Pozmix 2% gel, 3% cc by B.J. Titan. Recovered 2474' of 4 1/2" casing.  
(If additional description is necessary, use BACK of this form.)

STATE CORPORATION COMMISSION

INVOICED

(With this report) observe this plugging.

JAN 18 1990

Signed Stephen J. Pfeifer  
(TECHNICIAN)

DATE 1-29-90

INV. NO. 27226  
1-9

CONSERVATION DIVISION  
Wichita, Kansas