

120349

12-1 15-007-01019-00-01

To: 1  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- Drill Completion Date 1/9/46

NE NE SW, SEC. 19, T 30 S, R 11 W/E  
2310 feet from S section line  
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5893

Lease Name Wulf Well # A-1

Operator: Pratt Well Service, Inc.

County Barber 160.49

Name:

Address P.O. Box 847

Well Total Depth 4938 feet

Pratt, KS 67124

Conductor Pipe: Size feet

Surface Casing: Size 10 3/4 feet 415

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D&A

Other well as hereinafter indicated

Plugging Contractor Pratt Well Service, Inc. License Number 5893

Address P.O. Box 847, Pratt, KS 67124

Company to plug at: Hour: 12 p.m. Day: 1 Month: 12 Year: 19 89

Plugging proposal received from Bruce Wagner

(company name) Pratt Well Service, Inc. (phone) 316-672-2431

were: 4 1/2" casing at ? PBSD 4534' Perfs at 4444-48, 4452-62'

1st plug sand 4 1/2" casing back to 4394' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 10 3/4"

wiper plug and pump 100 sx cement.

STATE RECEIVED  
CONSERVATION COMMISSION  
WICHITA, KANSAS  
DEC - 15 1989

Plugging Proposal Received by Duane Rankin (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 3 p.m. Day: 1 Month: 12 Year: 19 89

ACTUAL PLUGGING REPORT 1st plug sanded 4 1/2" casing back to 4394' and dumped 4 sx cement, on top of sand through bailer,

2nd plug pumped into 8 5/8" surface casing with 350 lbs. hulls, 10 sx gel, 50 sx cement,

10 sx gel, 50 lbs. hulls, release 10 3/4" wiper plug and 150 sx cement.

Pumping pressure 0-500 psi and shut in 250 psi.

Leaked on backside-cut off 4' of casing and welded plate.

Remarks: Used 60/40 Pozmix 6% gel by B.J. Titan. Recovered 2489' of 4 1/2" casing.

(If additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE DEC 14 1989

Signed Duane Rankin (TECHNICIAN)

INV. NO. 26806

12-1 FEB 09 1990