

2 100059

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 077-21,102-00-00

DE \_\_\_\_\_, SEC. 14, T 35 S, R 7 **WXX**

\_\_\_\_\_ 330 feet from N/S section line

\_\_\_\_\_ 330 feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # \_\_\_\_\_ 5171

Lease Name Hopkins F Well # 1

Operator: TXO Production Corporation

County Harper 133.25

Name & Address 200 W. Douglas, #300

Well Total Depth 4100 feet

Wichita, KS 67202

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 275

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor H-30 Drilling License Number 5107

Address Wichita, KS

Company to plug at: Hour: \_\_\_\_\_ Day: 4 Month: 9 Year: 19 85

Plugging proposal received from Woody

(company name) H-30 Drilling (phone) \_\_\_\_\_

were: 950 feet - 35 sacks

325 feet - 35 sacks

60 feet - 25 sacks

Rat hole - 10 sacks

Mouse hole - 10 sacks

Plugging Proposal Received by Steve Van Gieson (TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None

Operations Completed: Hour: 10:15 a.m. Day: 5 Month: 9 Year: 19 85

ACTUAL PLUGGING REPORT Filled hole with heavy mud to 950 feet. Ran drill pipe to 950 feet and spotted 35 sacks of cement. Pulled pipe to 350 feet and spotted 35 sacks of cement. Ran wood and rubber plug to 60 feet and circulated 25 sacks of cement to surface. Ran one joint of drill pipe in rat hole and circulated 10 sacks of cement and 10 sacks in mouse hole.

STATE CORPORATION COMMISSION

Remarks: B.J. Titaln #28311 SEP 18 1985

(If additional description is necessary, use BACK of this form.)

INVOICED

DATE 9-18-85

INV. NO. 10157

CONSERVATION DIVISION  
Wichita, Kansas

Signed J.L. Sanders (TECHNICIAN)