

1 080280

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15-007-21,937-0000

R ✓

NW SW SE, SEC. 14, T 32 S, R 11 W/8

990 feet from (S) section line

2310 feet from (E) section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name Hrencher Well # 3

Operator: Hummon Corporation

County Barber

Name & Address 400 One Main Place

Well Total Depth 3767 ^{122.43} feet

Wichita, KS 67202

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 208

Abandoned Oil Well Gas Well _____ Input Well _____ SWD Well _____ D&A _____

Other well as hereinafter indicated _____

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 11:00 am Day: 13 Month: December Year: 19 84

Plugging proposal received from Elmo Morgenstern

(company name) Clarke (phone) 316-886-5665

were: 4 1/2" set at 3695' PBDT 3443' Perfs at 3612-3616' & 2583-2586'

1st plug push plug to 2560' and sand back to 2530 and dump 4 sx cement on top of sand through bailer

2nd plug squeeze well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 125 sx cement

Plugging Proposal Received by J. H. Metz (TECHNICIAN)

Plugging Operations attended by Agent?: All Part _____ None _____

Operations Completed: Hour: 12:50 pm Day: 13 Month: December Year: 19 84

ACTUAL PLUGGING REPORT 4 1/2" set at 3695' PBDT 3443' Perfs at 3612-3616' & 2583-2586'

1st plug pushed plug to 2560'. Sanded back to 2530' and dumped 4 sx cement on top of sand through bailer, 2nd plug squeezed well with 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sack hulls and 125 sx cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 15 1984
CONSERVATION DIVISION
Wichita, Kansas

Maximum pressure 750 psi and shut in 700 psi

Remarks: Recovered 1870' 4 1/2" casing. Used 60/40 Pozmix 2% gel 3% cc by Sun (If additional description is necessary, use BACK of this form.)

(I did ~~not~~) observe this plugging.

DATE 12-26-84

Signed *J. H. Metz* (TECHNICIAN)

INV. NO. 6162