

1 080607

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 007-21,816-0000

SE SE NE, SEC. 14, T 32 S, R 11 W/E

2970 feet from S section line

330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 6769

Lease Name Platt Well # 1

Operator: Westmore Drilling

County Barber 123.50

Name & Address Chapin Building

Well Total Depth 3800 feet

Medicine Lodge, KS 67104

Conductor Pipe: Size \_\_\_\_\_ feet

Surface Casing: Size 8 5/8 feet 265

Abandoned Oil Well \_\_\_\_\_ Gas Well  Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Clarke Corporation License Number 5105

Address Box 187, Medicine Lodge, KS 67104

Company to plug at: Hour: 10 a.m. Day: 30 Month: 4 Year: 19 87

Plugging proposal received from Elmo Morgenstein

(company name) Clarke Corporation (phone) 316-886-5665

were: 5 1/2" at 3798' PBSD 3700' Perfs at 2574-80'

1st plug sand up to 2525' and dump 5 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 15 sx gel, 50 sx cement, 10 sx gel and 120 sx cement.

Plugging Proposal Received by Don Ubel  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 12 p.m. Day: 30 Month: 4 Year: 1987

ACTUAL PLUGGING REPORT 1st plug sanded back to 2525' and dumped 5 sx cement on top of sand through bailer,

2nd plug pumped 3 sx hulls, 15 sx gel, 50 sx cement, 4 sx gel, and 120 sx cement.

Maximum pressure 900 psi and shut in 500 psi.

Remarks: Recovered 2000' of 5 1/2" casing. Used 60/40 Pozmix 6% gel by B. J. Titan.  
(If additional description is necessary, use BACK of STATE CORPORATION COMMISSION

**INVOICED**

DATE 5-4-87

INV. NO. 16713

Signed J. A. [Signature] 5-1-87  
(TECHNICIAN)

STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
Wichita, Kansas