

8-15-88

1 040154

API NUMBER 15-007-21,775-0000

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

SW SE SE, SEC. 14, T 32 S, R 11 W/E

330 feet from S section line

990 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5050

Lease Name Clarence Well # 1

Operator: Hummon Corporation

County Barber 123.50

Name & Address 400 One Main Place

Well Total Depth 3800 feet

Wichita, KS 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 223

Abandoned Oil Well Gas Well X Input Well SWD Well D&A

Other well as hereinafter indicated

Plugging Contractor Great Bend Casing Pullers Inc. License Number 4635

Address Box 768, Great Bend, KS 67530

Company to plug at: Hour: 1:30 p.m. Day: 15 Month: 8 Year: 19 88

Plugging proposal received from Gary Burke

(company name) Great Bend Casing Pullers Inc. (phone) 316-793-9711

were: 4 1/2" at 2690' PBTD 2644' Perfs at 2572-76' Elevation 1526' KB

1st plug sand back to 2520' and dump 4 sx cement on top of sand through bailer,

2nd plug pump 3 sx hulls, 10 sx gel, 50 sx cement, 10 sx gel, 1 sx hulls, release 8 5/8"

wiper plug and pump 120 sx cement.

RECEIVED  
STATE CORPORATION COMMISSION  
8-23-88  
AUG 23 1988  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Paul Luthi (TECHNICIAN)

Plugging Operations attended by Agent?: All X Part None

Operations Completed: Hour: 2:30 p.m. Day: 15 Month: 8 Year: 19 88

ACTUAL PLUGGING: 1st plug sanded back to 2520' and dumped 4 sx cement on top of sand through bailer,

2nd plug pumped down 8 5/8" with 300 lbs. hulls, 10 sx gel, 50 sx cement, 10 sx gel, 100 lbs. hulls, ans 120 sx cement.

Maximum pressure 1000 psi and shut in 500 psi.

Remarks: Used 60/40 Pozmix 6% gel by Allied. Recovered 2070' of 4 1/2" casing. (If additional description is necessary, use BACK of this form.)

INVOICED  
Observe this plugging.

DATE 8-24-88

Signed Stephen J. Pfeifer (TECHNICIAN)

INV. NO. 21896