

2 040473

1-3

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 077-20,193-00-00

SW NE NW, SEC. 20, T 34 S, R 9 W

4620 feet from S section line

3630 feet from E section line

## TECHNICIAN'S PLUGGING REPORT

Operator License # 3243

Lease Name Hagar Well # A-1

Operator: Commonwealth Petro Corp.

County Harper 150.48

Name &amp; Address P. O. Box 2458

Well Total Depth 4630 feet

Hutchinson, KS 67504

Conductor Pipe: Size feet

Surface Casing: Size 8-5/8 feet 228

Abandoned Oil Well Gas Well X Input Well SWD Well D&amp;A

Other well as hereinafter indicated

Plugging Contractor Nicholas Casing Pulling License Number 6698

Address 404 Silver, Geneseo, KS 67441

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Alan Nicholas

(company name) Nicholas Casing Pulling (phone)

were: 4-1/2" 4616' OH 4616-30' Bridge at 4400' - 50' of sand and

2 sx cement - 35 sx 1400', 25 sx 900', 35 sx 278', gel to 60' and cement to

0.

RECEIVED  
STATE CORPORATION COMMISSION  
STATE CORPORATION CC

JAN 18 1989

Plugging Proposal Received by CONSERVATION DIVISION  
SVG Wichita, Kansas  
(TECHNICIAN)

Plugging Operations attended by Agent?: All Part X None

Operations Completed: Hour: 16:15 Day: 3 Month: 1 Year: 19 89

ACTUAL PLUGGING REPORT A bridge was built at 4400' - 50' of sand was dumped on the

bridge and capped with 2 sx cement - the 4-1/2" was recovered from 3500' - 25

sx cement plug was spotted at 1400' and 900' thru the 4-1/2" casing - a 35

sx plug was spotted at 278' - 5 joints of 4-1/2" casing was pulled from the

well and circulated to 60' with gel. - the 4-1/2" was pulled to 60' and

circulated to 0' with cement.

Remarks: HOWCO #722629 60/40 poz 2% gel

(if additional description is necessary, use BACK of this form.)

INVOICED

observe this plugging.

DATE 1-20-89

WV. NO. 22733

Signed (TECHNICIAN)