

STATE OF KANSAS
STATE CORPORATION COMMISSION
200 Colorado Derby Building
Wichita, Kansas 67202

WELL PLUGGING RECORD
K.A.R.-82-3-117

API NUMBER 15-007-22,400-0000

LEASE NAME Alexander

TYPE OR PRINT
NOTICE: Fill out completely
and return to Cons. Div.
office within 30 days.

WELL NUMBER #1-2

500 Ft. from S Section Line

3960 Ft. from E Section Line

SEC. 2 TWP. 30 SRGE. 14 (X) or (W)

LEASE OPERATOR F.G. Holl Company

COUNTY Barber

ADDRESS P.O. Box 780167, Wichita, Ks. 67278-0167

PHONE# (316) 995-3171 OPERATORS LICENSE NO. 5056

Date Well Completed 6-1-92

Character of Well Dry hole

3:00 a.m.

(Oil, Gas, D&A, SWD, Input, Water Supply Well)

Plugging Commenced 6-1-92

4:30 a.m.

Plugging Completed 6-1-92

The plugging proposal was approved on may 29, 1992 (date)

by Steve Middleton, District #1 (KCC District Agent's Name).

Is ACO-1 filled? No If not, is well log attached? Yes

Producing Formation Arbuckle Depth to Top 4633' Bottom 4675' T.D. 4675'

Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS | CASING RECORD

Formation	Content	From	To	Size	Put In	Pulled out
Top soil & sand		0'	110'			
Red Bed		110'	240'	13-3/8"	234'	NONE

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet each set.

Plugged as follows: Heavy mud to 850' w/50 sacks at 850', heavy mud at 270' w/125 sacks at 270' heavy mud to 60' w/40 sacks at 60', 15 sacks in rathole. all of the above plugs were runned through open ended drill pipe. Job completed at 4:30 a.m. 6-1-92 by HOWCO, Inc. State Pluggger Steve Middleton, was not present. Sterling Drilling Company representative Vaughn Thompson was.
(If additional description is necessary, use BACK of this form.)

Name of Plugging Contractor Sterling Drilling Company LI KANSAS CORPORATION COMMISSION

Address PO Box 129, Sterling, Kansas 67579-0129

STATE OF Kansas COUNTY OF Rice, ss. JUN 4 1992

(Employee of Operation Conservation Division) of above-described well, being first duly sworn on oath, says: That I have known the facts, statements, and matters herein contained and the log of the above-described well as filed that the same are true and correct, so help me God.


(Signature) F.A. Wuellner

(Address) F.A. Wuellner, Sec./Treas. P.O. Box 129, Sterling, Ks. 67579-0129

SUBSCRIBED AND SWORN TO before me this 3rd day of June, 19 92

Agnes D. Wurst
Notary Public Agnes D. Wurst

My Commission Expires: 4-26-93



Used 60 X 40 pozmix with 6% gel.

STATE OF KANSAS
JAMES D. WELLS
1963