

WELL PLUGGING RECORD


STATE OF KANSAS
STATE CORPORATION COMMISSION

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
800 Bittling Building
Wichita, Kansas

Barber County, Sec. 2 Twp. 30S Rge. 14 (W)

Location as "NE/CNWxSWx" or footage from lines SE SE SW
Lease Owner Ashton Oil Company, Inc.
Lease Name Alexander Well No. 1
Office Address 402 A. C. Office Building - Arkansas City, Kansas
Character of Well (completed as Oil, Gas or Dry Hole) Dry hole
Date well completed 11-10 19 55.
Application for plugging filed 11- 9 19 55
Application for plugging approved 11- 9 19 55
Plugging commenced 11-10 19 55
Plugging completed 11-10 19 55
Reason for abandonment of well or producing formation Dry hole

NORTH



Locate well correctly on above Section Plat

If a producing well is abandoned, date of last production 19
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well R. Durkee
Producing formation Depth to top Bottom Total Depth of Well 4740 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

| FORMATION | CONTENT | FROM | TO | SIZE | PUT IN | PULLED OUT |
|--------------|---------|------|------|--------|--------|------------|
| Hebner Shale | | 3792 | | | | |
| Douglas Sand | | 3834 | | 8 5/8" | 327' | |
| Lansing Lime | | 3983 | 4316 | | | |
| Marmaton | | 4338 | | | | |
| Viola Lime | | 4464 | 4490 | | | |
| Simpson Sand | | 4595 | 4630 | | | |
| Arbuckle | | 4717 | 4735 | | | |

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from feet to feet for each plug set.

Mud to 300'. Halliburton plug set W/20 sacks cement on top. Mud to 35'. Halliburton plug set W/1 sack hulls 10 sacks cement.

VED
COMMISSION
NOV 25 1955
11-25-55
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor L. C. Smitherman Drilling Company
Address Box 627 - Augusta, Kansas

STATE OF Kansas, COUNTY OF Butler, ss.
Employee of owner (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Joe W. Cain
Douglass, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 23rd day of November 1955
Notary Public.

My commission expires October 23, 1958

PLUGGING
FILE SEC 2 T 30 R 14 W
BOOK PAGE 15 LINE 35

ALEXANDER #1

Company - Ashton Oil Company, Inc.
 Contractor - L. C. Smitherman Drig. Co.
 Commenced - 10-22-55
 Completed - 11-10-55
 Total Depth - 4740'
 Initial Prod. - D & A

Location: SE SE SW, ~~SW/4~~ Section
 2-30S-14W, Barber County,
 Kansas
 Elevation:
 Casing: 8 5/8" - 327' cemented W/
 300 Sacks.

Figures Indicate Bottoms of Formation:

| Depth | Formation |
|-------------|-------------------------------|
| 0 - 15 | Soil |
| 15 - 110 | Sand |
| 110 - 150 | Shale |
| 150 - 225 | Shale & Shells |
| 225 - 318 | Shale & Red Rock |
| 318 - 327 | Lime & Shale |
| 327 - 402 | Lime & Shale |
| 402 - 495 | Shale & Shells |
| 495 - 890 | Shale & Red Rock |
| 890 - 920 | Lime |
| 920 - 1460 | Shale & Lime Shells |
| 1460 - 1932 | Shale & Shells |
| 1932 - 2075 | Lime |
| 2075 - 2140 | Shale |
| 2140 - 2365 | Lime & Shale |
| 2365 - 2445 | Lime (F. R.) |
| 2445 - 2585 | Lime & Shale Strks. |
| 2585 - 2925 | Lime & Shale |
| 2925 - 3125 | Shale & Lime |
| 3125 - 3175 | Lime |
| 3175 - 3185 | Shale & Lime |
| 3185 - 3278 | Lime & Shale |
| 3278 - 3360 | Lime (Topeka) |
| 3360 - 3444 | Lime W/Shale Strks. |
| 3444 - 3704 | Lime, Shale |
| 3704 - 3760 | Lime |
| 3760 - 3853 | Lime & Sand |
| 3853 - 3980 | Sand & Shale |
| 3980 - 4015 | Lime (Lansing) |
| 4015 - 4053 | Lime "Cherty" |
| 4053 - 4122 | Lime (KC) |
| 4122 - 4131 | Lime & Sand |
| 4131 - 4367 | Lime (KC) |
| 4367 - 4418 | Lime & Shale |
| 4418 - 4428 | Core #1 |
| 4428 - 4462 | Lime |
| 4462 - 4481 | Core #2 |
| 4481 - 4548 | Lime |
| 4548 - 4564 | Lime & Chert |
| 4564 - 4592 | Chert W/Shale |
| 4592 - 4616 | Shale & Chert - Sand Streaks |
| 4616 - 4626 | Lime & Sand |
| 4626 - 4656 | Cherty Shale & Sand (Simpson) |
| 4656 - 4677 | Shale & Sand |
| 4677 - 4740 | Shale & Lime |

RECEIVED
 STATE CORPORATION COMMISSION
 NOV 25 1955
 11-25-55
 CONSERVATION DIVISION
 Wichita, Kansas

We hereby certify the above and foregoing to be a true and correct copy of the Log on the Alexander #1, located in the SE SE SW, SW/4 of Section 2-30S-14W, Barber County, Kansas.

L. C. SMITHERMAN DRILLING COMPANY

C. H. Moore

Subscribed and sworn to before me this 19th day of November, 1955.

Keith W. Carter
 Notary Public

My commission expires October 23, 1958.

PLUGGING
 FILE NO. 2-30-14W
 BOOK PAGE 15 LINE 35