


WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Barber County, Sec. 2 Twp. 30S Rge. 14 (E) W (W)  
Location as "NE/CNW/SW" or footage from lines NW NE NE  
Lease Owner Bowers Drilling Company  
Lease Name Staats Well No. #1  
Office Address 1434 Wichita Plaza; Wichita, Kansas 67202  
Character of Well (completed as Oil, Gas or Dry Hole)  
Date well completed 19  
Application for plugging filed July 19 69  
Application for plugging approved July 19 69  
Plugging commenced August 7 19 69  
Plugging completed August 8 19 69  
Reason for abandonment of well or producing formation

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes

Name of Conservation Agent who supervised plugging of this well Ralph Warren  
Producing formation Depth to top Bottom Total Depth of Well Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
				8 5/8	407	None
				4 1/2	4194	2030

8-29-69  
RECEIVED  
STATE CORPORATION COMMISSION  
AUG 28 1969  
CONSERVATION DIVISION  
Wichita, Kansas

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth of each plug set.

8 - 7 - 69 Dumped sand to 2250'. Mixed and dumped 4 sx of cement to 2200', to plug off bottom.  
8 - 8 - 69 Set 10' rock bridge from 220' to 230', Mixed and dumped 25 sx of cement. Mudded casing (8 5/8) to 40'. Set 10' rock bridge from 40' to 30'. Mixed and dumped 10 sx of cement from 30' to base of cellar.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor Russ Casing Pulling, Inc.  
Address P. O. Box 1082 Great Bend, Kansas 67530

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Emil E. Bowers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers  
1434 Wichita Plaza Bldg., Wichita, Kansas  
29th August 69 (Address)

SUBSCRIBED AND SWORN TO before me this 29th day of August, 1969

My commission expires May 12, 1973  
Carole A. Young Notary Public.

WELL LOG

COMPANY:	Bowers Drilling Company, Inc.
CONTRACTOR:	Bowers Drilling Company, Inc.
FARM:	#1 Staats
LOCATION:	NW NE NE Section 2-30S-14W Barber County, Kansas
COMMENCED:	9-20-67
COMPLETED:	10-5-67
ELEVATION:	1970 Kelly Bushing

0 - 1185	Sand Shell	8-5/8" set at 407' W/250 sax
1185 - 1760	Shale	
1760 - 2095	Shale & Lime	
2095 - 2270	Lime	
2270 - 3410	Lime & Shale	
3410 - 3752	Lime	
3752 - 3875	Lime & Shale	
3875 - 4430	Lime	4-1/2" set at 4194' W/525 sax
4430 - 4467	Lime & Sand	
4467 - 4529	Arbuckle	
4529 -	TD	

LOG TOPS

Heebner	3761 (-1791)
Toronto	3780 (-1810)
Douglas Shale	3804 (-1834)
Douglas Sand	3819 (-1849)
Brown Lime	3936 (-1966)
Lansing/Kansas City	3950 (-1980)
Base/Kansas City	4332 (-2362)
Marmaton	4353 (-2383)
Simpson	4400 (-2430)
Arbuckle	4432 (-2462)
LTD	4527 (-2557)

RECEIVED  
STATE CORPORATION COMMISSION  
7-24-69  
JUL 24 1969  
CONSERVATION DIVISION  
Wichita, Kansas

STATE OF KANSAS        )  
                                  ) SS  
COUNTY OF SEDGWICK    )

I, Emil E. Bowers, do hereby certify that the above and foregoing is a true and correct copy of the log of the Staats #1 located NW NE NE of Section 2-30S-14W Barber County, Kansas, as reflected by the files of Bowers Drilling Company, Inc.

*Emil E. Bowers*

Subscribed and sworn to before me, a Notary Public, in and for Sedgwick County, Kansas this 12th day of October, 1967.

*Elaine L. Winter*  
Elaine L. Winter, Notary Public

My Commission expires May 5, 1970.