

15-007-30322-0000


STATE OF KANSAS
STATE CORPORATION COMMISSION

Form CP-4

WELL PLUGGING RECORD

Give All Information Completely
Make Required Affidavit
Mail or Deliver Report to:
Conservation Division
State Corporation Commission
P. O. Box 17027
Wichita, Kansas 67217
NORTH

Barber County, Sec. 19 Twp 32 Rge (E) 11 (W)
Location as "NE/CNW/SE/SW" or footage from lines S/2 SE NW
Lease Owner Phillips Petroleum Company
Lease Name Bungarner Well No. 1
Office Address Box 287, Great Bend, Kansas 67530
Character of Well (completed as Oil, Gas or Dry Hole) oil
Date well completed 10
Application for plugging filed Nov. 8 10 73
Application for plugging approved 10
Plugging commenced Dec. 18 10 73
Plugging completed Dec. 22 10 73
Reason for abandonment of well or producing formation depleted



Locate well correctly on above
Section Plat

If a producing well is abandoned, date of last production 10
Was permission obtained from the Conservation Division or its agents before plugging was commenced? YES

Name of Conservation Agent who supervised plugging of this well G. R. Biberstein
Producing formation _____ Depth to top _____ Bottom _____ Total Depth of Well 4357 Feet
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
		0	221'	8 5/8"	221'	none
			3629'	4 1/2"	3629'	3079.45

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from _____ feet to _____ feet for each plug set.

Allied Cementing Company pumped 50 sacks of cement to bottom of well to plug it off. Pumped plug on top of cement; stopped plug at 3450'

Allied Cementing Company plugged well pumping in 2 sacks of hulls, 15 sacks of gel and 100 sacks of cement.

RECEIVED
STATE CORPORATION COMMISSION
DEC 26 1973
12-26-73
CONSERVATION DIVISION
Wichita, Kansas

(If additional description is necessary, use BACK of this sheet)
Name of Plugging Contractor PIPE PULLERS, INC.
Address Box 486, Ellinwood, Kansas 67526

STATE OF KANSAS COUNTY OF BARTON ss.
Evelyn Roth (employee of owner) or (owner or operator) of the above-described

well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Evelyn Roth
Ellinwood, Kansas (Address)

SUBSCRIBED AND SWORN TO before me this 24th day of December 19 73

My commission expires Feb. 10, 1975
George A. Meyer Notary Public

ROTARY DRILLING LOG

Operator: Beardmore Drilling Co.
 #1 Bumgarner
 S/2 SE NW Sec. 19-32S-11W
 Barber County, Kansas

Contractor: Rains & Williamson Oil Co.
 Commenced: 11-28-66
 Rotary Released: 12-9-66
 Remarks: Set 221.29' of 8-5/8" surface casing with 175 sacks common cement w/2% calcium chloride.

Set 4-1/2" casing at 3629'
 with 100 sacks common cement.

FORMATIONS

Sand	20'
Shale & Red Bed	640'
Red Bed & Shale	1285'
Shale & Shells	1610'
Shale & Lime	1875'
Lime	1975'
Lime & Shale	2125'
Shale & Lime	2670'
Shale w/Lime	2910'
Shale & Lime	3435'
Lime & Shale	3535'
Sand	3581'
Shale & Sand	3705'
Lime	4302'
Lime & Chert	4336'
Chert	4357'
Rotary Total Depth	4357'

RECEIVED
 STATE CORPORATION COMMISSION
 AUG 10 1973
 8-10-73
 CONSERVATION DIVISION
 Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.
Wilson Rains
 Wilson Rains

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 13th day of December 1966.

My Commission Expires:
 3-3-70

Mary J. Brown
 Mary J. Brown, Notary Public

15-057-38322-0000
ROTARY DRILLING LOG

Operator: Beardmore Drilling Co.
#1 Bumgarner
S/2 SE NW Sec. 19-328-11W
Barber County, Kansas

Contractor: Rains & Williamson Oil Co.
Commenced: 11-28-66
Rotary Released: 12-9-66
Remarks: Set 221.29' of 8-5/8" surface casing with 175 sacks common cement w/2% calcium chloride.

Set 4-1/2" casing at 3629' with 100 sacks common cement.

FORMATIONS

Sand	20'
Shale & Red Bed	640'
Red Bed & Shale	1285'
Shale & Shells	1610'
Shale & Lime	1875'
Lime	1975'
Lime & Shale	2125'
Shale & Lime	2670'
Shale w/Lime	2910'
Shale & Lime	3435'
Lime & Shale	3535'
Sand	3581'
Shale & Sand	3705'
Lime	4302'
Lime & Chert	4336'
Chert	4357'
Rotary Total Depth	4357'

RECEIVED
STATE CORPORATION COMMISSION
NOV 9 1973
11-8-73
CONSERVATION DIVISION
Wichita, Kansas

We certify the above log is true and correct to the best of our knowledge and belief.

RAINS & WILLIAMSON OIL CO.

Wilson Rains
Wilson Rains

Subscribed and sworn to before me, a Notary Public in and for the State of Kansas, County of Sedgwick, this 13th day of December 1966.

My Commission Expires:

3-3-70

Mary J. Brown
Mary J. Brown, Notary Public