


K-007-2127-0000

WELL PLUGGING RECORD

Give All Information Completely  
Make Required Affidavit  
Mail or Deliver Report to:  
Conservation Division  
State Corporation Commission  
212 No. Market  
Wichita, Kansas

NORTH



Locate well correctly on above  
Section Plat

Barber County, Sec. 19 Twp. 32S Rge. (E) 11 (W)  
Location as "NE/CNWKSW" or footage from lines C/SL NE NW NW  
Lease Owner Bowers Drilling Company, Inc.  
Lease Name Willms Well No. 1  
Office Address 125 No. Market, Suite 1425 Wichita, Kansas  
Character of Well (completed as Oil, Gas or Dry Hole) Dry Hole  
Date well completed August 12 19 81  
Application for plugging filed August 12 19 81  
Application for plugging approved orally August 12 19 81  
Plugging commenced August 12 19 81  
Plugging completed August 12 19 81  
Reason for abandonment of well or producing formation Dry Hole

If a producing well is abandoned, date of last production 19  
Was permission obtained from the Conservation Division or its agents before plugging was commenced? Yes - Orally

Name of Conservation Agent who supervised plugging of this well Maurice Leslie  
Producing formation \_\_\_\_\_ Depth to top \_\_\_\_\_ Bottom \_\_\_\_\_ Total Depth of Well \_\_\_\_\_ Feet  
Show depth and thickness of all water, oil and gas formations.

OIL, GAS OR WATER RECORDS

CASING RECORD

FORMATION	CONTENT	FROM	TO	SIZE	PUT IN	PULLED OUT
Surface		0	206	8 5/8	206'	0

Describe in detail the manner in which the well was plugged, indicating where the mud fluid was placed and the method or methods used in introducing it into the hole. If cement or other plugs were used, state the character of same and depth placed, from \_\_\_\_\_ feet to \_\_\_\_\_ feet for each plug set.

Filled hole with heavy mud to 200', set plug with 50 sax cement, heavy mud to 40', set plug with 10 sax cement. 10 sax cement in rat hole.

(If additional description is necessary, use BACK of this sheet)

Name of Plugging Contractor \_\_\_\_\_  
Address \_\_\_\_\_

STATE OF KANSAS, COUNTY OF SEDGWICK, ss.  
Emil E. Bowers (employee of owner) or (owner or operator) of the above-described well, being first duly sworn on oath, says: That I have knowledge of the facts, statements, and matters herein contained and the log of the above-described well as filed and that the same are true and correct. So help me God.

(Signature) Emil E. Bowers  
125 No. Market, Suite 1425 Wichita, Kansas 67202  
(Address)

SUBSCRIBED AND SWORN to before me this 7th day of October

My commission expires March 2, 1984

RECEIVED  
STATE CORPORATION COMMISSION  
OCT 13 1981  
K-13-81  
CONSERVATION DIVISION  
Wichita, Kansas

15-007-2727-0000

GABBERT-JONES, INC.  
WICHITA, KANSAS  
DRILLERS' WELL LOG

Willms #1  
165' E of NW-NW  
Sec 19-32S-11W  
Barber County Kansas

Commenced: 8-6-81

Completed: 8-12-81

OPERATOR: BOWERS DRILLING CO.

From	Depth To	Formation	Remarks
0	100	Sand-Clay-Redbed	Ran 5 jts of 22# 8 5/8" csg set @ 206' Cemented w/ 175 sks Common 2% Gel 3% CC PD @ 8:40 p.m. 8-6-81
100	212	Redbed-Sand	
212	653	Redbed	
653	1285	Redbed-Shale	
1285	1561	Shale-Lime	
1561	2175	Shale	
2175	2415	Shale-Lime	
2415	2595	Lime-Shale	
2595	3080	Shale-Lime	
3080	3200	Lime-Shale	
3200	3507	Shale-Lime	
3507	3559	Lime-Shale	
	3559 - TD		DRY & ABANDONED

STATE OF KANSAS )  
                          ) SS  
COUNTY OF SEDGWICK)

I, the undersigned, being duly sworn on oath, state that the above Drillers' Well Log is true and correct to the best of my knowledge and belief and according to the records of this office.

GABBERT-JONES, INC.

*James S. Sutton II*  
JAMES S. SUTTON II

Subscribed and sworn to before me this 13th day of August, 1981.

*Elizabeth J. Edwards*  
ELIZABETH J. EDWARDS-NOTARY PUBLIC

My Commission expires February 6, 1983.

