

KANSAS
STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. P. Roberts
Assistant Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Operator's Full Name E. K. Edmiston

Complete Address: 501 First National Bank Bldg., Wichita, Kansas

Lease Name Warwick-Allender Well No. # 1

Location C NW SE Sec. 12 Twp. 31 Rge. 11 (E) (W)W

County Barber Total Depth 4600'

Abandoned Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated: _____

Plugging Contractor: Southwest Casing Pulling Company

Address: Box 364, Great Bend, Kansas License No. 399

Operation Completed: Hour 9:45 AM Day 7th Month Feb. Year 1966

The Above well was plugged as follows:

265' of 8 5/8" surface pipe, cement circulated. 4600' of 4 1/2" long string, cemented with 125 sacks. Plug back to 4565'. Top perforation 4519'. Bottom of the hole was sanded to 4500', and cemented with 3 sacks, through the dump bailer. 3935' of 4 1/2" long string was recovered from the hole. Hole was bailed down to a fluid level of 260', bridge plug and rock bridge from 260' to 250', and cemented with 25 sacks. Hole was filled with mud to 40', rock bridge from 40' to 30', and cemented with 10 sacks to the base of the cellar.

I hereby certify that the above well was plugged as herein stated.

Signed: Annie Elving
Well Plugging Supervisor

INVOICED

DATE 2/8/66

INV. NO. 2696-W