

State of Kansas



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market

WICHITA, KANSAS

JEWEL M. OGDEN, Director

GEORGE DOCKING Governor
MARION BEATTY Chairman
HARRY G. WILES Commissioner
RICHARD C. BYRD Commissioner
RAYMOND B. HARVEY Secretary
CLYDE E. MILLIGAN Counsel

Handwritten initials 'CJB'

Jewel M. Ogden, Director
500 Insurance Building
212 North Market
Wichita 2, Kansas

Dear Sir:

I have this date November 15, 19 58, authorized the following plugging operation:

Operator's Full Name: Pickrell Drilling Co.

Complete Address: 705 Fourth National Bank Bldg., Wichita, Kans.

Lease Name: Tedrow Well No. 1

Location: CN SW SW Sec. 28 Twp. 32 Rge. 12 (E) (W) X

County: Barber Total Depth: 4575

Oil Well Gas Well Input Well SWD Well D & A X

Other well as hereafter indicated:

Operator was instructed to plug well as follows:

200' of 8 5/8" surface casing circulated with cement. Fill hole to 190' with heavy drilling mud. Set cementing plug at 190' with 20 sack cement top plug through drill pipe. Heavy mud to 40' with cementing plug placed at 40' and cement to base of cellar.

Very truly yours,

Signed: [Signature] Conservation Division Agent

RECEIVED STATE CORPORATION COMMISSION

NOV 19 1958

CONSERVATION DIVISION WICHITA, KANSAS