

R

KANSAS

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

J. Lewis Brock  
Administrator  
245 North Water  
Wichita, KS 67202

API Number 15 -007-20084-00-01 (of this well)

Operator's Full Name Jesus O. & Son, Corp.

Complete Address 200 W. Douglas, Suite 300, Wichita, Kans. 67202

Lease Name Tickens "A" Well No. 1

Location C-SW-NE- Sec. 21 Twp. 30<sup>5</sup> Rge. 14 (E) (W) X

County Barber Total Depth 4653

Abandoned Oil Well  Gas Well  Input Well  SWD Well  D & A

Other well as hereafter indicated \_\_\_\_\_

Plugging Contractor Pratt Well Service, Inc.

Address 723 S. Nimessech, Pratt, Mo. 67124 License No. 761

Operation Completed: Hour 2:30 pm Day 3 Month 2 Year 1979

The above well was plugged as follows:

206'-10 3/4" Casing - 980'-8 5/8" Casing Bottom Cemented - top orange  
peeled from 10 3/4" Casing to 8 5/8" Casing & welded to 8 5/8" Casing - 4 1/2" Casing  
set @ 4653' w/ 250 sac cement plug back to 4400' - set steel plug  
@ 4000' Top plug, 4068' - sand back to 3970' top sand w/ 4 sac mixed cement  
w/ dump hole & pull 3000' 4 1/2" Casing - set rock bridge @ 475'  
Fluoreo mixed & pumped 145 sac 50/50 permif. Cement from  
475' to top of Casing -

I hereby certify that the above well was plugged as herein stated.

INVOICED

DATE 2-7-79

INV. NO. 9077-W

RECEIVED  
STATE CORPORATION COMMISSION  
FEB - 6 1979  
2-6-79  
CONSERVATION DIVISION  
Wichita, Kansas

Signed: [Signature]  
Well Plugging Supervisor