

KANSAS

Form CP-3
Rev. 6-4-68

STATE CORPORATION COMMISSION

CONSERVATION DIVISION AGENT'S REPORT

RECEIVED
STATE CORPORATION COMMISSION

MAR 26 1975

CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
P. O. Box 17027
Wichita, Kansas 67217

Operator's Full Name Okmar Oil Co

Complete Address 970 4th Financial Center Wichita, KS

Lease Name Harbaugh D Well No. 1

Location E/2 W/2 NW Sec. 14 Twp. 33 Rge. 12 (E) (W)

County Barber Total Depth 4500

Abandoned Oil Well Gas Well Input Well SWD Well D & A

Other well as hereafter indicated _____

Plugging Contractor Southwest Casing Pulling Co Inc

Address Box 364 Great Bend, KS License No. 399

Operation Completed: Hour 4:00 PM Day 24 Month 3 Year 1975

The above well was plugged as follows:

405 ft 8 5/8 surface cemented with 350 sacks. 3920 ft 5 1/2 long
string cemented with 100 sacks. Top perf. 3807 ft. Sand to 3790 ft.
5 sacks cement with bailer. Pulled 2491 ft 5 1/2. Set 10 ft rock
bridge at 240 ft. Fill hole with 4 yds redimix to surface.

I hereby certify that the above well was plugged as herein stated.

Signed: [Signature]
Well Plugging Supervisor

INVOICED

DATE 3/26/75

INV. NO. 1050-w