

STATE OF KANSAS  
STATE CORPORATION COMMISSION  
CONSERVATION DIVISION  
200 Colorado Derby Building  
Wichita, Kansas 67202

FORM CP-1  
Rev. 03/92

WELL PLUGGING APPLICATION FORM  
(PLEASE TYPE FORM and file ONE copy)

API # 15-007-22385-00-00 (Identifier number of this well). This must be listed for wells drilled since 1967; if no API# was issued, indicate spud or completion date.

WELL OPERATOR RAYDON EXPLORATION, INC. KCC LICENSE # 30604

ADDRESS P.O. BOX 1816 (owner/company name) CITY LIBERAL (operator's)

STATE KANSAS ZIP CODE 67905-1816 CONTACT PHONE # (316) 624-0156

LEASE DONOVAN WELL# 1-9 SEC. 9 T. 34S R. 13 (East/West)

NE - NW SPOT LOCATION/COORD COUNTY BARBER

530 FEET (In exact footage) FROM S(N) (circle one) LINE OF SECTION (NOT Lease/LINE)

3310 FEET (In exact footage) FROM E/W (circle one) LINE OF SECTION (NOT Lease/LINE)

Check ONE: OIL WELL  GAS WELL  D&A  SWD/ENHR WELL  DOCKET#

CONDUCTOR CASING SIZE  SET AT  CEMENTED WITH  SACKS

SURFACE CASING SIZE 8 5/8 SET AT 433 CEMENTED WITH 181 SACKS

PRODUCTION CASING SIZE 4 1/2 SET AT 5077 CEMENTED WITH 150 SACKS

LIST (ALL) PERFORATIONS and BRIDGEPLUG SETS: 4866-72 4873-89 4935-50

ELEVATION 1786/1798 T.D. 5075 PETD 5051 ANHYDRITE DEPTH (Stone Corral Formation)  
(G.L./K.S.)

CONDITION OF WELL: GOOD  POOR  CASING LEAK  JUNK IN HOLE

PROPOSED METHOD OF PLUGGING MIX & PUMP 25SX CEMENT PLUG, DISPLACE W/9.2# MUD FROM 4500'-4780'

FREEPOINT & CUT CSG. PULL TO 1500', MIX & PUMP 40SX CEMENT 1500'-1400'. PULL TO 550', MIX

& PUMP 70SX CEMENT 550' TO 380'. PULL CSG TO 40', CIRCULATE 10SX CEMENT TO SURFACE.

(If additional space is needed attach separate page)

IS WELL LOG ATTACHED TO THIS APPLICATION AS REQUIRED? YES IS ACO-1 FILED? YES

If not explain why? \_\_\_\_\_

PLUGGING OF THIS WELL WILL BE DONE IN ACCORDANCE WITH K.S.A. 55-101 et. seq. AND THE RULES AND REGULATIONS OF THE STATE CORPORATION COMMISSION.

LIST NAME OF COMPANY REPRESENTATIVE AUTHORIZED TO BE IN CHARGE OF PLUGGING OPERATIONS:

KEITH HILL CROWN CONSULTING INC PHONE# ( ) 316-624-0156

ADDRESS P.O. BOX 1816 City/State LIBERAL, KANSAS 67905-1816

PLUGGING CONTRACTOR JERRY DUNKIN, INC. KCC LICENSE # 08733

ADDRESS P.O. BOX 389 ENID, OK 73702 (company name) PHONE # ( ) 405-237-6152 (contractor's)

PROPOSED DATE AND HOUR OF PLUGGING (If known?) 3-26-96

PAYMENT OF THE PLUGGING FEE (K.A.R. 82-3-118) WILL BE GUARANTEED BY OPERATOR OR AGENT

DATE: 3-25-96 AUTHORIZED OPERATOR/AGENT: [Signature]

(signature)

12/96  
RECEIVED  
KANSAS CORPORATION COMMISSION  
3-26-96

D



## Kansas Corporation Commission

Bill Graves, Governor Susan M. Seltsam, Chair F.S. Jack Alexander, Commissioner Timothy E. McKee, Commissioner  
Judith McConnell, Executive Director David J. Heinemann, General Counsel

### NOTICE OF RECEIPT OF WELL PLUGGING APPLICATION (CP-1)

March 27, 1996

Raydon Exploration Inc  
P O Box 1816  
Liberal KS 67905-1816

Donovan #1-9  
API 15-007-22,385  
530 FNL 3310 FEL  
Sec. 09-34S-13W  
Barber County

Dear Keith Hill Crown Consulting, Inc.,

This letter is to notify you that the Conservation Division is in receipt of your plugging proposal, form CP-1, for the above-captioned well.

Your CP-1 has been reviewed by the Conservation Division central office for completeness and to verify license numbers. The plugging proposal will now be forwarded to the district office listed below for review of your proposed method of plugging.

Please contact the district office for approval of your proposed plugging method at least at five (5) days before plugging the well, pursuant to K.A.R. 82-3-113 (b). If a workover pit will be used during the plugging of the well it must be permitted. A CDP-1 form must be filed and approved prior to the use of the pit.

The Conservation Division's review of form CP-1, either in the central or district office, does not include an inquiry into well ownership or the filing operator's legal right to plug the well.

This notice in no way constitutes authorization to plug the above-captioned well by persons not having legal rights of ownership or interest in the well. This notice is void after ninety (90) days from the above date.

Sincerely,

A handwritten signature in cursive script that reads "David P. Williams".

David P. Williams  
Production Supervisor

District: #1  
304 W. McArtor  
Dodge City, KS 67801  
(316) 225-6760